

**REMON. COR. K-8, CITY OF MIDLAND  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

475

For corners in  
Midland  
(County)

Located in:	Corner Code #
T <u>14N</u> R <u>2E</u>	<u>K-8</u>
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

1. Public Land Survey
2. Property Controlling in Section
3. Miscellaneous Property in Sec.
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
MIDLAND COUNTY  
REMONUMENTATION & FILED

12/15/1999 8:26:43 AM

SCOTT I. HAINES  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, RODNEY CLAYPOOL, in a field survey on August 11, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-8 1/4 Corner common to Sections 23 and 24

Survey by Glo, 1830's, set post  
Survey by Edmands Engineering, 1971, 1972, 1973, 1990, 1991, monument box  
Survey by Hunter-Whittier, 1972, 1975, 1978, found  
Survey by A. Leach, 1978, found iron in monument box  
Survey by D. Ledy, 1988, 1989, found nail  
LCRC by E. Goss, 1973, nail

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-8 1/4 Corner common to Sections 23 and 24

Found 1/2" rod in concrete road in monument box per surveys by Edmands Engineering, Hunter-Whittier, A. Leach, D. Ledy and LCRC by E. Goss.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-8 1/4 Corner common to Sections 23 and 24

Set brass cap stamped Midland Co. Remon Cor PS 29241 on 1/2" rod in concrete in monument box, and is accepted as the best available evidence of the position of the accepted corner.

S 43 Deg E, 91.74', Northwest building corner (Brick)  
S 55 Deg E, 59.96', Northwest bolt on traffic light pole base  
N 40 Deg E, 65.44', Southwest bolt on traffic light pole base (Rec.)  
N 45 Deg W, 57.84', Southeast bolt on traffic light pole base (Rec.)  
S 35 Deg W, 56.32', Northeast bolt on traffic light pole base  
S 20 Deg W, 59.28', centerline top fire hydrant (Rec.)



SURVEY &  
REMONUMENTATION

FEB 09 2000

SECTION

Signed by Rodney D. Claypool  
Surveyor's Michigan License No. 29241

Date 12-11-99  
Form approved by Michigan State Board of Land Surveyors, Jan. 28, 1971  
Revised May 14, 1971  
Revised Jan., 1983

REMON. COR. K-8  
P.A. 345 OF 1990  
MIDLAND COUNTY

11/23/99