

REMON. COR. K-9, CITY OF MIDLAND  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
MIDLAND COUNTY  
REMONUMENTATION & FILED

12/15/1999 8:26:43 AM

SCOTT I. HAINES  
REGISTER OF DEEDS

For corners in  
Midland  
(County)

Located in: Corner Code #

1. Public Land Survey

T 14N R 2E K-9

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

2. Property Controlling  
in Section

S \_\_\_ T \_\_\_ R \_\_\_

S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous  
Property in Sec.

S \_\_\_ T \_\_\_ R \_\_\_

S \_\_\_ T \_\_\_ R \_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, RODNEY CLAYPOOL, in a field survey on August 12, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-9 Corner common to Sections 23, 24, 25 and 26

Survey by Glo, 1830's, set post  
Survey by J. Schafer, 1977, found monument  
Survey by Wade-Trim, 1990, found pk nail  
LCRC by D. Whittier, 1972, found monument

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-9 Corner common to Sections 23, 24, 25 and 26

Found pk nail over hub per surveys by J. Schafer, Wade-Trim and LCRC by D. Whittier.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-9 Corner common to Sections 23, 24, 25 and 26

Replaced pk nail with 5/8" rod and brass cap stamped Midland Co. Remon Cor PS 29241 in monument box, and is accepted as the best available evidence of the position of the accepted corner.

N 60 Deg W, 44.38', centerline top fire hydrant (Rec.)  
N 30 Deg W, 52.67', pk nail in power pole  
S 30 Deg E, 75.72', Northwest bolt on railroad signal light pole base  
South, 56.90', South edge North rail railroad tracks (Rec.)

Signed by Rodney D. Claypool  
Surveyor's Michigan License No. 29241

Date 12-11-99  
Form approved by Michigan State Board of Land Surveyors, Jan. 28, 1971  
Revised May 14, 1971  
Revised Jan., 1983

Register of Deeds Stamp & File Number

|    |    |    |    |    |    |    |   |   |   |   |   |   |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A  | B  | C  | D  | E  | F  | G  | H | I | J | K | L | M |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

SURVEY &  
REMONUMENTATION

FEB 09 2000

SECTION

AS PER MIDLAND COUNTY  
P.A. 245 OF 1990  
MIDLAND COUNTY

11/23/99 JG

