

NOV 07 1994

COMMISSION

REMON. COR. L-11, CITY OF MIDLAND LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

2/24/94

75

For corners in Midland

Table with columns: (County), Located in:, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec.

STATE OF MICHIGAN MIDLAND COUNTY REMONUMENTATION & FILED

15 MAR 94 9:03 A.M.

BEVERLY J THAYER REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

A B C D E F G H I J K L M


Grid table with rows 2-13 and columns A-M containing numbers 1-36.

I, RODNEY CLAYPOOL, in a field survey on NOVEMBER 19, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-11 Corner common Sec. 25 and 36 Wood post Government survey 1830's Pine 22", N 68 Deg W, 38 1/2 L (25.41') Hemlock 16", S 74 Deg E, 17 L (11.22') Survey by Dow 1951, 3/4" pipe in approximate line of fence to North Southeasterly, 109.2' to NE corner well HS Northeasterly, 39.4' to centerline 8" Oak Southwesterly, 126.65' to face power pole Survey by Edmands Engineering 1977, 1978 Found 1" pipe WSW 127.02' to centerline power pole WNW 148.63' to centerline power pole #288-1 S 0.6' to PHY centerline E-W road Survey by M. MacDonald 1984, found 1" pipe S 45.5' to ground at N face of 4" pipe with valve NE 65.6' to MBT cable sign Survey by J. Jones 1984, Found 3/4" pipe in pavement N 50 Deg E, centerline of Bell cable manhole, 68.21' S 10 Deg W, centerline of stem on valve wheel brine line 49.12' 0.85' N of centerline pavement LCRC by D. Whittier 1972 Found 3/4" pipe S 5 Deg E, NE corner #9 salt well, 109.15' S 2 Deg E, NW corner #9 salt well, 105.73' About 0.6' North of centerline of blacktop of Salzburg Road



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-11 Corner Common to Sec. 25 and 36 Found rerod and cap (replaced rod and cap with 5/8" rod and brass cap) per surveys by Dow, Edmands Engineering, M. MacDonald, J. Jones, and LCRC by D. Whittier

Corner L-11 was approved for remonumentation at a Peer Review Committee Meeting on FEB 24 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-11 Corner common to Sec. 25 and 36 Found rod and cap (replaced rod and cap with 5/8" rod and brass cap stamped Midland Co. Remon. Cor. PS 29241 in mon box) per surveys by Dow, Edmands Engineering, M. MacDonald, J. Jones, and LCRC by D. Whittier and is accepted as the best available evidence of the position of the original corner N 45 Deg W, 143.66', nail and plastic disc in power pole N 55 Deg E, 210.63', nail and plastic disc in power pole N 55 Deg W, 97.7', centerline Michigan Bell Telephone manhole N 40 Deg E, 68.2', centerline Michigan Bell Telephone manhole

Signed by Rodney D. Claypool Date 03-07-94

Surveyor's Michigan License No. 29241