

APPROVED LAND CORNER
P.A. 345 OF 1990
MIDLAND COUNTY

REMON. COR. I-6, HOMER TWP.
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

318

2/22/1979

For corners in
Midland
(County)

	Located in:	Corner Code #
1. Public Land Survey	T <u>14N</u> R <u>1E</u>	<u>I-6</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
MIDLAND COUNTY
REMONUMENTATION & FILED

8 DEC 97 11:03 A.M.

BEVERLY J THAYER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, RODNEY CLAYPOOL, in a field survey on APRIL 9, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- I-6 Corner common to Sections 14 and 15
- 1831, government survey by H. Park, set corner
- 1910, survey of Sec 14 by Gibbs, set post
- 1915, survey of Sec 15 by Gibbs, set gas pipe
- No date, H-W witness cards, set 3/4" pipe, found remains of old corner post
- 1955, Survey by Hunter, no call
- 1971, survey by Schafer, found 3/4" iron (witness card)
- 1975, LCRC #385 by Hooth, found 3/4" pipe
- 1977, rec. survey by Schafer, L-2, P-226, mon box
- 1979, Rec survey by Schafer, L-2, P-952, found 3/4" pipe in mon box
- 1988, rec. survey by Ledy, L-4, P-297, found pipe in mon box

SURVEY &
REMONUMENTATION

FEB 24 1998

SECTION



WITNESS NOTE: Witnesses from above surveys and LCRC's are available in dossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- I-6 Corner common to Sections 14 and 15
- Found 3/4" pipe in mon box per surveys by F. Gibbs, M. Hunter, J. Schafer, D. Ledy, H-W witness card and LCRC by Hooth.

Corner I-6 was approved for remonumentation at a Peer Review Committee Meeting on July 22, 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-6 Corner common to Sections 14 and 15
- Found 3/4" pipe in mon box, replaced pipe with new 3/4" pipe and brass cap stamped Midland Co. Remon Cor. PS 29241, per surveys by F. Gibbs, M. Hunter, J. Schafer, D. Ledy, H-W witness card, and LCRC by Hooth; and is accepted as the best available evidence of the position of the accepted corner.
- S 89 Deg E, 38.74', nail and disc in power pole
- S 40 Deg W, 53.98', spike in 42" Maple (R)
- S 25 Deg W, 74.85', nail and plastic disc in 36" Oak
- N 85 Deg W, 54.35', nail and disc in power pole
- S 40 Deg W, 53.45', nail and disc in 42" Maple
- East, 0.8', center line road

Signed by Rodney D. Claypool Date 11-26-97

Surveyor's Michigan License No. 29241

Form approved by Michigan State Board of Land Surveyors, Jan. 28, 1971

Revised May 14, 1971

Revised Jan., 1983