

APPROVED LAND CORNER  
P.A. 345 OF 1990  
MIDLAND COUNTY

JAN 21 1999

REMON. COR. K-12, HOMER TWP.  
SECTION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

402

STATE OF MICHIGAN  
MIDLAND COUNTY  
REMONUMENTATION & FILED

12/16/1998 12:11:56 PM

BEVERLY J. THAYER  
REGISTER OF DEEDS

For corners in  
Midland

(County)

Located in: Corner Code #

- 1. Public Land Survey T 14N R 1E K-12  
T R  
T R  
T R
- 2. Property Controlling in Section S T R  
S T R
- 3. Miscellaneous Property in Sec. S T R  
S T R
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

I, JERRY L. JONES, in a field survey on JULY 23, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- K-12 Corner common to Sections 35 and 36  
Glo survey, 1830's, set post  
Survey and LCRC by J. Schafer, 1976, 1978, set 3/4" shaft  
Survey by J. Jones, 1990

WITNESS NOTE: Witnesses from above surveys and LCRC's are available in dossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- K-12 Corner common to Sections 35 and 36  
Found 1/2" rod per surveys by J. Schafer, J. Jones and LCRC by J. Schafer

Corner K-12 was approved for remonumentation at a Peer Review Committee Meeting on 9/9/98.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-12 Corner common to Sections 35 and 36  
Found 1/2" rod per surveys by J. Schafer, J. Jones and LCRC by J. Schafer, replaced rod with 5/8" rod and brass cap stamped Midland Co. Remon Cor. PS 29241, and mon box, and is accepted as the best available evidence of the position of the accepted corner.  
  
S 30 Deg W, 29.82', spike in 12" Ash  
N 30 Deg W, 20.93', pk in guard rail post  
N 30 Deg E, 22.63', pk in guard rail post  
North, 4.0', centerline Stewart Road  
West, 34.0', to centerline drain  
S 60 Deg E, 25.60', mag nail in guard rail post

Signed by Jerry L. Jones Date 12/14/98

Surveyor's Michigan License No. 19838