

APPROVED LAND CORNER  
P.A. 345 OF 1990 LAND CORNER RECORDATION CERTIFICATE  
MIDLAND COUNTY Filing Requirement of Act 74, Mich. P.A. 1970  
Midland County Remonumentation

STATE OF MICHIGAN  
MIDLAND COUNTY  
RECORDED

12/7/1999 2:59:31 PM

SCOTT I. HAINES  
REGISTER OF DEEDS

9/17/99 [Signature]

For Corners in Midland (County)

	Located In:	Corner Code#:
1. Public Land Survey	T. <u>14</u> R. <u>2W</u>	<u>M-9</u>
	T. <u>14</u> R. <u>1W</u>	<u>A-9</u>
	T. _____ R. _____	_____
2. Public Controlling in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
3. Miscellaneous Property in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on 6-28-1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1830 Clark  
Cor Sec's 24 & 25  
W. Ash 6, N 21 W 12  
Maple 6, S 45 W 4  
1978 Fluharty, LCRC, 455  
Set 5/8" x 18" re-rod in wooded area  
(Note on LCRC says this is wrong  
three witnesses same as 1st 3 in LCRC 465)
- 1852 Burt  
Int. W. Bdg. 37 links S of the Cor.  
Sec 24 & 25, S 89° 43' E corrected  
between Sec 19 & 30  
Maple 6, S65E 14  
W. Pine 14, N39 E 38  
1978 Lapham, LCRC, 465  
Fd 5/8" capped rod  
N33E 15.78 3" Maple  
S65W 31.12 Twin Oak  
S53E 21.69 10" Oak  
S10E 7.95 4" Maple in clump

SURVEY &  
REMONUMENTATION

FEB 25 2000

SECTION

1910 Gibbs, C.S.R.  
Set Post. Old Pine 14" N39E 38

1920 Gibbs, C.S.R.  
Fd oak post in survey of Sec 25, 1910

1923 Gibbs, C.S.R.  
Old Cor. Post standing

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 1" pipe 2640.33 South of M-8/A-8 and at a deflection angle of 0° 12' left of M-7 to M-8 extended South. M-7 to M-8 Meas. 2639.60. Found four 1978 witnesses.

Corner M-9, T14N, R2W and A-9 T14N, R1W were approved for remonumentation at a Peer Review Committee Meeting on 9/17/99

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Std. Midland County Remon Cap marked, P.S. 27458 on existing 1" pipe. Placed Mon. Box at corner. Accepted as best available evidence of the accepted position of the corner.

- Witnesses:
- S80°W 30.90', set spike in North 12" Twin Oak (OBT)
  - S40°E 21.73', set spike in 18" Oak (OBT)
  - N55°E 11.55', set spike in 8" Oak
  - N40°W 25.55', set spike in 6" Maple

Signed by Mark R. Robison  
Surveyor's Michigan License No. 27458



Date 11-22-99