

Sequence # 1

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

7
STATE OF MICHIGAN
MIDLAND COUNTY
REMONUMENTATION & FILED

For corners in

Midland County	Located In:	Corner Code #
1. Public Land Survey	T 14N R 1W	E-5
	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

30 NOV 93 3:07 P.M.

BEVERLY J THAYER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	A
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5					●								
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Norman C. Caldwell, in a field survey on May, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E-5) Sec. Cor. 8, 9, 16, & 17, T14N-R1W

Wood Post placed by Austin Burt in 1852 Subd. resurvey S27°E 11 L.(7.26') 7" Tamarack N59°W 17 L.(11.22') 8" Tamarack

Survey D. Ledy, Recorded in L. 4 P. 587 of Surveys, Found 1/2" bar: North 23.70' CL M-20; S80°E 90.00' Gas Line Marker; S40°W 65.95' P. Pole.

NOTE: 6-23-93 & 9-13-93 Ledy used position 16' S. of Centerline

Survey by J. Jones, Recorded in L. 2 P. 100 of Surveys, Found 1/2" pipe: S45°W 72.59' N&T in P.Pole; N40°W 84.17' N&T in P. Pole; North 16' +- CL M-20.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E-5) Sec. Cor. 8, 9, 16 & 17, T14N-R1W

Found 1/2" Iron Pipe w/cap per L. 2, P. 303, L. 1, P. 605, L. 2 P. 100 of Surveys and a conflicting 1/2" bar S 0°59'15" E, 7.60.

E-5 Approved by Midland County Peer Group November 3, 1993
C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E-5) Sec. Cor. 8, 9, 16 & 17, T14N-R1W

Fnd 1/2" Iron Pipe as recorded in L. 4 P. 587 and L. 2 P. 100 of Surveys, and on MDOOT R/W maps, and is accepted as the best available evidence of the position of the original corner.
S40°W 72.46' Power Pole (R)
S25°E 98.99' 10" Maple
S21°E 145.55' Power Pole
N20°W 84.10' Power Pole (R)
North 16' +- CL M-20
S 0°59'15" E 7.60' 1/2" Bar



Signed by Norman C. Caldwell

Date 29 NOV 93

Surveyor's Michigan License No. 12018