

APPROVED FOR RECORDATION  
 P.A. 345 OF 1997  
 MIDLAND COUNTY

MIDLAND COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

360

8/01/97 *[Signature]*

For corners in

MIDLAND (County)	Located In:	Corner Code #
1. Public Land Survey	T 14N R 1W	H-13 ✓
	T 13N R 1W	H-1
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

STATE OF MICHIGAN  
 MIDLAND COUNTY  
 FILED &  
*REMONUMENTATION*  
 11 DEC 97 12:03 P.M.  
 BEVERLY J THAYER  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, **MARK R. ROBISON**, in a field survey on July 1, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

SURVEY &  
 REMONUMENTATION  
 FEB 24 1998  
 SECTION

A. Description of original monument and accessories and/or subsequent restoration:  
 1831 Clark Post  
 Wit.-Elm 13 N84 1/2E 46  
 Pine 35 N08W 17  
 10-75 Schafer (132) 1-956  
 Fd. 2" Pipe  
 Wit.-North 12.56 tag in P.P. Stub  
 North 50 degrees - 44.56 tag in P.P.  
 N40W 75.59 tag in Oak Clump  
 10-20-80 Lapham, L.C.R.C. 527  
 Fd 3/4" Pipe  
 Wit.-South 32.85 Capped Iron  
 North 12.75 Post  
 N60E 44.65 P.P.  
 N60W 52.30 6" Maple

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Found 3/4" x 18" pipe two feet deep in new constructed road. Found one 1975 witness. Meas. East 2635.08 (Schafer 2634.98) to I-13. Did not find 2" pipe. Major road re-construction has removed all other witnesses. Found old fence to South 32 ft. West.

Corners, H-13, T14N, R1W, & H-1, T13N, R1W, were approved for remonumentation at a Peer Review committee Meeting on 08/01/97 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Set 3/4" x 18" Gas Pipe with Brass Cap stamped "Midland Co. Remon. Cor. P.S. 27458" in Monument Box. Accepted as best available evidence of the accepted position of the corner.  
 Witnesses:  
 N45W 75.59', nail & tag, in Oak Clump (OBT)  
 N43E 40.08', nail & tag, P.P  
 N61W 73.45', nail & tag, Twin 12" oak  
 S45W 76.62', nail & tag, 14" W. Oak  
 S29E 72.72', nail & tag, 13" W. Oak

Signed by *Mark R. Robison*  
 Surveyor's Michigan License No. 27458

Date 10-31-97

