

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMMISSION

STATE OF MICHIGAN  
MIDLAND COUNTY  
REMONUMENTATION & FILED

REMONUMENTATION

|                                       |                         |               |
|---------------------------------------|-------------------------|---------------|
| <u>Midland</u><br>(County)            | Located In:             | Corner Code # |
| 1. Public Land Survey                 | T 14N R 1W              | 1-6           |
|                                       | T _____ R _____         | _____         |
|                                       | T _____ R _____         | _____         |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____ | _____         |
|                                       | S _____ T _____ R _____ | _____         |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____ | _____         |
|                                       | S _____ T _____ R _____ | _____         |
| 4. Lot No. _____, Recorded Plat _____ |                         |               |
| 5. Private Claims _____               |                         |               |

30 NOV 93 3:08 P.M.

BEVERLY J THAYER  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Norman C. Caldwell, in a field survey on May, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

|    |    |   |    |   |    |   |    |   |    |   |    |   |   |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(1-6) 1/4 Cor. Sec. 14 & 15, T14N-R1W

Post Placed by Austin Burt  
in 1852 Subd. Resurvey  
S37°E 27 L.(17.82') 12" Maple  
N57°W 27 L.(17.82') 22" Maple

L.C.R.C. by P. Lapham, Recorded in Bk. 1 P. 623,  
Found 3/4" Pipe in Mon. Box: N60°E 47.33' 20"  
Oak; East 33.0' Capped Rod; N80°W 51.5' P. Pole.  
(Surveys in L. 2, P. 567, L. 4, P. 464)  
(Recorded Plat of McConnell Sub., L. G, P. 19)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(1-6) 1/4 Cor. Sec. 14 & 15, T14N-R1W

Found 1" Pipe over 5/8" Re Rod per Bk.1 P. 623,  
Record Mon. Box apparently destroyed. Placed new Mon. Box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(1-6) 1/4 Cor. Sec. 14 & 15, T14N-R1W

Found 1" Pipe over 5/8" Re Rod per Bk. 1 P 623,  
Placed Mon Box and is accepted as the best  
available evidence of the position of the  
original corner.

N76°W 51.47' Power Pole(R)  
East 32.95' 1/2" Re Rod & cap #9433(R)  
N75°E 56.00' 8" Oak  
N23°E 115.64' 8" Oak



Signed by Norman C. Caldwell

Date 24 NOV 93

Surveyor's Michigan License No. 12018