

APPROVED LAND CORNER  
P.A. 345 OF 1990  
MIDLAND COUNTY

Midland County Remonumentation

*Sequence #2*

232

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

*7/18/95*

For corners in Midland (County) Located In: Corner Code #

1. Public Land Survey	T	<u>14N</u>	R	<u>1W</u>	<u>K 5</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____

*Seq. 2*

STATE OF MICHIGAN  
MIDLAND COUNTY  
REMONUMENTATION & FILED

14 AUG 95 3:02 P.M.

BEVERLY J THAYER  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Craig W. McVean, in a field survey on June, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

1. Description of original monument and accessories and/or subsequent restoration:  
K 5 Midland County Remonumentation L.C.R.C. - Remonumentation L. 1, P. 15 - found 1/2" pipe in monument box - Caldwell - 1993.

2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
K 5 Recorded monument obliterated during 1994-1995 reconstruction of Highway M-20. Found broken off Pk nail in agreement with remonumentation L.C.R.C. Witnesses.  
Also see Dossier on file at Midland County Register of Deeds.



3. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
K 5 Replace Pk nail with 2" Midland County brass cap on 5/8" x 24" rebar in monument box.  
S 58° E 100.54' 6" Red Pine (R).  
S 30° E 108.40' 8" Black Oak (R).  
S 80° E 140.06' to nail and tag in S side 18" Poplar.  
S 40° W 112.79' to NE corner of Tavern.  
S 45° W 157.50' to NW corner of Tavern.  
S 70° W 39.74' to Pk in N side U.P.

Signed by Craig W. McVean Date 7/6/95  
Surveyor's Michigan License No. 39088