

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
MIDLAND COUNTY
REMONUMENTATION & FILED

COMMISSION

For corners in

Midland County

Located In:

REMONUMENTATION
Corner Code #

30 NOV 93 3:09 P.M.

BEVERLY J THAYER
REGISTER OF DEEDS

- 1. Public Land Survey T 14N R R1W L-5
- 2. Property Controlling in Section S T R
- 3. Miscellaneous Property in Sec. S T R

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
- 5. Private Claims

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Norman C. Caldwell, in a field survey on May, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(L-5) 1/4 Cor., Sec. 12 & 13, T14N-R1W

Post Placed by Austin Burt in 1852 Subd. Resurvey. N56°W 12 L.(7.92') 14" Black Ash S04°E 10 L.(6.6') 18" White Pine

L.C.R.C. by D. Ledy, Recorded in Bk. 1 P. 645, Set 3/8" Rod 3' long per L. 1 P. 647: North 157.33' 1/2" Pipe @ S'ly R/W M-20; NW 128.63' SW Cor Hse; ESE 23.05' 60d in 6" Willow; SE 30.42' 60d in 8" Ash. (Surveys in L. 1, P. 647 & L. 2, P. 78)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(L-5) 1/4 Cor., Sec. 12 & 13, T14N-R1W

Found 3/8" Iron Rod w/cap #21575 per Bk.1 P.645.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(L-5) 1/4 Cor., Sec. 12 & 13, T14N-R1W

Fnd 3/8" Iron Rod w/cap#21575 per B 1,P645 and survey recorded in L 1,P 647 and is accepted as the best available evidence of the position of the original corner.

N62°W 128.62' SE cor Hse #237(R)
S32°E 30.41' 8" Ash
S65°E 23.04' 6" Willow(R)
S45°E 2.32' Fence Cor Post (E&W)



Signed by *Norman C. Caldwell*
Surveyor's Michigan License No. 12018

Date 24 NOV 93