

JAN 21 1999

MIDLAND COUNTY  
P.A. 345 OF 1990  
MIDLAND COUNTY

MIDLAND County Remonumentation

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

376

For corners in 9/09/98

<u>MIDLAND</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T14N R01W	L-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN  
MIDLAND COUNTY  
REMONUMENTATION & FILED

12/16/1998 12:11:56 PM

BEVERLY J. THAYER  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Mark R Robison, in a field survey on September, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

L-11: 1852 Burt  
West 40.33 to 1/4 Post  
Wit-1)W. Pine 14 S48E 38 lks  
2)Maple 6" N43E 12 lks

3-27-85 Ledy  
Set 1/2" pipe on line between K-11 & M-11 at double distance between K-11 & found West 1/8 Corner on North line of Section 36. (Found West 1/8 corner which is 3/4" Iron Pipe, 1.70 feet North of Sec line)  
Wit-1)South 32.90 Nail in 30" Oak  
2)North 35.03 Nail in P.P.  
3)SW 44.1 Nail in Post

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
L-11: Found 3/4" x 20" pinched pipe. Excavated to 3 feet and found no other evidence. Measured West 1342.31 to 1/8 corner; reading on fence line North (Did not excavate). Measured 2683.82 West to Section Corner. Measured East 2660.27 to Section Corner. Found and checked 1985 witnesses. Fence line to South.

Corner, L-11, was approved for remonumentation at a Peer Review Committee Meeting on 9/10 9/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
L-11: Set 3/4" x 18" Gas Pipe with Brass Cap stamped "Midland Co. Remon. Cor. P.S.27458" in Monument Box. Accepted as best available evidence of the accepted position of the corner.

Witnesses:  
South 32.90', nail & tag, 36" Oak (OBT)  
N06E 35.03', nail & tag, P.P. (OBT)  
SW 44.10', nail & tag, Post (OBT)  
N35W 75.57', nail & tag, West 12" Twin Maple



Signed by Mark R. Robison  
Surveyor's Michigan License No. 27458

Date 12-09-98