

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

1839

For corners in

REMONUMENTATION

STATE OF MICHIGAN
MIDLAND COUNTY
REMONUMENTATION & FILED

30 NOV 93 3:09 P.M.

BEVERLY J THAYER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Midland (County)	Located In:	Corner Code #
1. Public Land Survey	T 14N R 1W	M-6
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	A
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Norman C. Caldwell, in a field survey on May, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(M-6) Standard East 1/4 Cor, Sec 13, T14N-R1W

Post Placed by Robert Clarke Jr.
in 1830 Original Survey
N19°W 66 L.(43.56') 5" Pine
N21°W 129 L.(85.14') 3" Tamarack

L.C.R.C. by M. Bennett, Recorded in Bk.1 P. 381,
Found 1/2" Re-Rod in Mon. Box: S40°W 56.08'
T.Pole; S85°E 83.83' 16" Oak; N70°W 56.52' 5" Poplar.
(Survey in L. 3, P. 470

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M-6) Standard East 1/4 Cor, Sec.13, T14N-R1W

Found 5/8" Bar in Mon. Box per Bk. 1 P. 381.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M-6) Standard East 1/4 Cor, Sec.13, T14N-R1W

Found 5/8" Bar in Mon. Box per Bk. 1 P. 381 and is accepted as the best available evidence of the position of the original corner.

West 57.00' Fence Cor Post
S47°W 52.78' 12" White Pine
N60°E 75.73' 4" White Pine
S85°E 84.04' 20" Oak(R)
North Closing cor. E-8

479.30'



Signed by Norman C. Caldwell
Surveyor's Michigan License No. 12018

Date 29 NOV 93