

JAN 21 1999

APPROVED FORM 1971  
T.A. 845 OF 1970  
MIDLAND COUNTY

MIDLAND County Remonumentation

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

377

For corners in 9/09/98 JOR

_____ MIDLAND _____ (County)	Located in:	Corner Code #
1. Public Land Survey	T14N R01W	M-11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
MIDLAND COUNTY  
REMONUMENTATION & FILED

12/16/1998 12:11:56 PM

BEVERLY J. THAYER  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Mark R Robison, in a field survey on September, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

M-11: 1830 Clark Cor Sec 25 & 36  
Wit-1)Pine 10" N13W 22  
2)Aspen 4 S30W 20

1830 Clark  
NW Cor T13N, R1E falls 6.91 ch North of  
25-36 Sec Cor T14N, R1W

1960 MDOT  
1" Iron Pin 8" Deep 458.22' South of  
Closing corner (Twp Cor)  
Wit-1)N60W 67.44 T.P.  
2)N30W 51.88 10" Poplar  
3)West 2.20 Survey Line  
4)N88E 29.61 NW Cor General Store

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-11: Found 3/4" x 24" Iron in Monument Box 2 feet West of centerline of pavement. Measured West 2660.27 feet to 1/4 Corner. Measured North 457.99 (GLO 456.06, MDOT 458.22) to NW Cor Sec 1, T14N, R1E. MDOT witnesses of T.P., 10" Poplar, and General Store are gone.

Corner, M-11, was approved for remonumentation at a Peer Review Committee Meeting on 9/09/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-11: Set 3/4" x 18" Gas Pipe with Brass Cap stamped "Midland Co. Remon. cor. P.S.27458" in Monument Box. Accepted as best available evidence of the accepted position of the corner.

Witnesses:  
N17W 84.00', nail & tag, P.P.  
S15E 105.14', nail & tag, P.P.  
S63W 86.50' NW Corner Gordonville Cafe  
S27E 109.62', nail & tag, 32" Ash



Signed by Mark R. Robison

Date 12-09-98

Surveyor's Michigan License No. 27458