

APPROVED LAND CORNER

P.A. 345 OF 1990  
MIDLAND COUNTY

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970  
Midland County Remonumentation

480

8/24/00

For Corners in  
Midland

(County)

Located In: Corner Code#:

- 1. Public Land Survey T. 14N R. 1W E-13  
T. 13N R. 1W E-1  
T. \_\_\_\_\_ R. \_\_\_\_\_
- 2. Public Controlling S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_  
in Section S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_
- 3. Miscellaneous S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_  
Property in Section S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

**SURVEY &  
REMONUMENTATION**  
**FEB 23 2001**

**SECTION**

STATE OF MICHIGAN  
MIDLAND COUNTY  
REMONUMENTATION & FILED

10/6/2000 10:36:48 AM

SCOTT I. HAINES  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on July 14, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

This is a single corner common to T13N, R01W & T14N, R01W.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1831, Clark,  
B. Oak 11" N67°E, 25 LINKS  
Pine 40" N60°W, 29 LINKS

1973, Schafer, (132) 1-369  
Same as LCRC #114  
Meas. N 1322.85' to 1/8 Cor  
Meas. W 2645.68' to 1/4 Cor

1971, Whittier, LCRC #114  
1" round rod Meas. East 2650.97  
S15°E, 22.4' NW Cor. Conc.  
guard wall to bridge  
S15°W 22.0' NE Cor. Conc.  
guard wall to bridge  
N45°E, 49.0' face of P.P.

1978, Schafer, (132) 2-566  
Survey in Section 5, T13N, R1W  
Establishes dist to West at 2645.8'


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Fd 1/2" x 10" pipe over 1" x 30" sq. bar. Top of bar is 1.2 feet deep. Found three 1971 witnesses. Meas. West 2645.80 to D-13/D-1. Meas. North 2645.62 to E-12. Accepted 1" bar as best available evidence of the perpetuation of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 18" pipe with brass cap stamped "Midland County Remon Cap, P.S #27458" in Mon. Box.

Witnesses:  
N45°E, 49.72' - N & T in P.P. (OBT)  
S36°E, 48.40' - N & T in P.P.  
S45°W, 81.40' - Cen. of N'y 4 x 4 Trip. Birch in yard  
N20°W, 74.90' - N & T in P.P.



Signed by Mark R. Robison  
Surveyor's Michigan License No. 27458

Date 9-15-2000