

APPROVED LAND CORNER
P.A. 345 OF 1990
MIDLAND COUNTY

MIDLAND COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

366

8/10/97

For corners in

<u>MIDLAND</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>14N</u> R <u>2W</u>	<u>A-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
MIDLAND COUNTY
FILED
REMONUMENTATION
11 DEC 97 12:04 P.M.

BEVERLY J THAYER
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, MARK R. ROBISON, in a field survey on July 1, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and I, that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1830 Wright
Post 103 lks North of Std. Cor.

10-03-86 Ankrom L.C.R.C. 620
Set rerod & cap at G.L.O. falling from
Standard Corner.
Wit.-South 66.00 SE Cor, Sec 24
N35E 54.69 20' W. Pine
N70E 58.00 12' W. Pine
West 15.28 South Leg Road Sign

SURVEY &
REMONUMENTATION

FEB 24 1998

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" x 24" rerod. Excavated and found no other evidence. Found all 1986 witnesses. Measured North 2641.80 ft. to A-8 and 2642.14 ft. more to A-7. Moved corner 1.98 ft. North to fit GLO falling of 67.98 ft. (1.03 ch).

Corner, A-9 was approved for remonumentation at a Peer Review Committee Meeting on 08/10/97 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 18" Brass cap stamped "Midland Co. Remon. Cor. P.S. 27458" in Monument Box. Accepted as best available evidence of accepted position of corner.

Witnesses:
South 67.98', 3/4" pipe at Standard Corner (OBT)
N35E 52.90', nail & tag, 34" W. Pine (OBT)
N70E 57.42', nail & tag, 28" W. Pine (OBT)
S66E 99.22', nail & tag, P.P.

Signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 10-31-97

