

1993

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

24

For corners in COMMISSION

Midland	Located in:	REMONUMENTATION	Corner Code #
(County)			
1. Public Land Survey	T <u>14N</u> R <u>2W</u>		<u>E-4</u>
	T _____ R _____		_____
	T _____ R _____		_____
	T _____ R _____		_____
2. Property Controlling in Section	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

STATE OF MICHIGAN  
MIDLAND COUNTY  
REMONUMENTATION & FILED

30 NOV 93 3:10 P.M.

BEVERLY J THAYER  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Norman C. Caldwell, in a field survey on May, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E-4) 1/4 Cor., Sec. 8 & 9, T14N-R2W

Wood Post Placed by Joel Whight in 1832  
Sub. of Twp.: S88°W 7 L. (1.408M) 12" (30.5cm)  
Hemlock; N72°E 25 L. (5.029M) 9" (23cm) Hemlock.

L.C.R.C. by J. Schafer, Recorded in Bk. 1 P. 247,  
Found 65mm Boiler Flue, Raised w/20mm Pipe:  
N60°W 21.565M Tag in 38cm Oak; N50°E 11.400M Rivet  
on N. End 30cm CMP; S45°E 14.96M CL underground  
Cable Marker.

L.C.R.C. by T. Mueller, Recorded in Bk. 1 P. 540,  
Found 20mm Pipe: NW 21.382 N&F 51cm Oak; SW  
15.712M Top CL S. End 30cm Culvert; SE 14.646M  
Top CL Cable Box.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E-4) 1/4 Cor., Sec. 8 & 9, T14N-R2W

Found 20mm Pipe per Bk. 1 Pgs. 247 & 540.  
Placed #12018 cap in Pipe and Mon. Box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E-4) 1/4 Cor., Sec. 8 & 9, T14N-R2W

Found 20mm Pipe per Bk. 1 Pgs. 247 & 540, Placed  
#12018 Cap in Pipe & Mon. Box, and is the best  
available evidence of the position of the  
original corner.

N48°E 11.348M Rivet on N end 30cm CMP(R)  
N60°W 21.350M 45cm Black Oak (R)  
S45°E 14.525M Buried Cable Sign Post (R)  
S78°E 18.379M Power Pole



Signed by Norman C. Caldwell

Date 10 NOV 93

Surveyor's Michigan License No. 12018

