

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

26

For corners in

COMMISSION

REMONUMENTATION

Midland _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>14N</u> R <u>2W</u>	<u>F-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
 MIDLAND COUNTY
 REMONUMENTATION & FILED

30 NOV 93 3:11 P.M.

BEVERLY J THAYER
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Norman C. Caldwell, in a field survey on May, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(F-5) 1/4 Cor., Sec. 9 & 16, T14N-R2W

Wood Post Placed by Joel Whight in 1832 Sub. of Twp.: S12°E 19 L.(3.822M) 16" (40cm) Maple; N30°W 18 L.(3.621M) 10" (25cm) Maple.

L.C.R.C. by D. Whittier, Recorded in Bk. 1 P. 213, Set 20mm Pipe from records: South 11.522M 78cm Pipe; N45°W 13.829M W. End Conc. Pipe; North 17.322M CL M-20; North 16.206M 20mm Bar.

L.C.R.C. by G. Gray, Recorded in Bk. 1 P.695, Found Capped 20mm Pipe: S11y 13.046M Face 65mm Gas Pipe Marker; SE 22.388M 15cm Scotch Pine; WSW 42.446M P. Pole; North 12.22M S. Edge M-20 Pavement.

Survey by Schafer, L. 1, pg. 308 Utilized this position

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F-5) 1/4 Cor., Sec. 9 & 16, T14N-R2W

Found 20mm Pipe per Bk. 1 Pgs. 213 & 695, L. 1, pg. 308

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F-5) 1/4 Cor., Sec. 9 & 16, T14N-R2W

Found 20mm Pipe per Bk.1 Pgs. 213 & 695, L. 1, pg. 308, and is accepted as the best available evidence of the position of the original corner.

S71°W 42.421M P.Pole(R)
 S02°W 13.058M 65mm Gas Line Marker(R)
 S42°E 22.404M 15cm Scotch Pine(R)
 S72°E 38.422M N&T in T. Pole
 North 17.300M CL M-20 (R)



Signed by Norman C. Caldwell
 Surveyor's Michigan License No. 12018

Date 16 NOV 93