

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
REMONUMENTATION

STATE OF MICHIGAN
MIDLAND COUNTY
REMONUMENTATION & FILED

For corners in

Midland _____ <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>14N</u> R <u>2W</u>	<u>G-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

30 NOV 93 3:11 P.M.

BEVERLY J THAYER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	I
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman C. Caldwell, in a field survey on May, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G-3) Sec. Cor. 3, 4, 9, & 10, T14N-R2W
 Post Placed by Joel Whight in 1832 Sub. of
 Twp: S59°W 30 L.(6.035M) 10" (25.5cm) Birch;
 N26°E 50 L.(10.058M) 12" (30.5cm) Black Ash.
 L.C.R.C. by T. Mueller, Recorded in Bk. 1 P. 540,
 Found large Spike: SW 15.042M 30cm Birch; SE
 19.17M 30cm Maple; NW 10.409M(?) 38cm Oak;
 NE 15.286M 20cm Ash.
 Survey by Ruddell, L. 3, pg. 550, utilized
 this position

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G-3) Sec. Cor. 3, 4, 9, & 10, T14N-R2W
 Found 13mm Rod per references in Bk. 1 P. 540
 & L. 3, pg. 550

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G-3) Sec. Cor. 3, 4, 9, & 10, T14N-R2W
 Found 13mm Rod per Bk. 1, P. 540 & L. 3,
 pg. 550 and is accepted as the best
 available evidence of the position of the
 original corner.
 S52°E 19.082M 30cm Maple (R)
 N32°W 15.526M 38cm Twin Black Oak
 N38°E 15.244M 25cm Elm (R)
 S24°E 31.474M 15cm White Pine



Signed by *Norman C. Caldwell*
 Surveyor's Michigan License No. 12018

Date 16 NOV 93