

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
REMONUMENTATION

STATE OF MICHIGAN
MIDLAND COUNTY
REMONUMENTATION & FILED

For corners in

Midland _____ Located In: _____ Corner Code # _____
(County)

- 1. Public Land Survey T 14N R 2W G-6
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

30 NOV 93 3:11 P.M.

BEVERLY J THAYER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Norman C. Caldwell, in a field survey on May, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G-6) 1/4 Cor., Sec. 15 & 16, T14N-R2W
Wood Post Placed by Joel Whight in 1832 Sub. of Twp.: N45°W 41 L.(8.248M) 36"(91cm) W. Oak; S20°E 14 L.(2.816M) 24" (61cm) Pine.
Unrecorded references by C.P. Co. in 1942, Solid Iron Axle 15cm Below Surface w/Broken Glass & Crockery; N7°E 47.838M P. Pole; S44°E 14.69M P. Pole.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G-6) 1/4 Cor., Sec. 15 & 16, T14N-R2W
Found 20mm Iron Pipe in Mon. Box as an apparent replacement of unrecorded axle shaft. Placed #12018 cap in pipe

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G-6) 1/4 Cor., Sec. 15 & 16, T14N-R2W
Found 20mm Iron Pipe in Mon Box as an apparent replacement of unrecorded axle shaft, Placed #12108 cap in pipe and is accepted as the best available evidence of the position of the original corner.
S46°W 22.766M N&W in P.Pole
N58°E 21.044M N&T 25cm White Pine
N86°E 17.358M N&T 20cm White Pine
S40°E 24.078M N&T 12cm White Pine



Signed by Norman C. Caldwell Date 16 NOV 93
Surveyor's Michigan License No. 12018