

APPROVED LAND CORNER
P.A. 345 OF 1990
MIDLAND COUNTY

310

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MIDLAND (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>14N</u> R <u>2W</u>	<u>G-11</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

STATE OF MICHIGAN
MIDLAND COUNTY
REMONUMENTATION & FILED

20 DEC 96 2:07 P.M.

BEVERLY J THAYER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, MARK R. ROBISON, in a field survey on AUGUST, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1830 WRIGHT
WIT.-SET POST.
BIRCH 10" S34°E 32 LKS.
B. ASH 12", N66°W 33 LKS.

8-27-79 CAMPBELL
WIT.-SET T-IRON BY PROPORTIONAL MEASURE
NE, 55.40' - TELE POLE.
SE, 19.40' - END C.M.P.
SW, 33.78' - END C.M.P.

NO DATE GIBBS, C.S.R.
WIT.-OLD POST
40.04 1/2' TO G-10

6-09-80 MUELLER
WIT.-FOUND T-IRON
NE, 55.40' - TELE. POLE.
SE, 19.40' - END OF C.M.P.
SW, 33.78' - END OF C.M.P.

11-14-07 GIBBS
WIT.-GAS PIPE FOR COR.
RESURVEY ON PAGES 238-239.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND T-IRON 8' EAST & 16' SOUTH OF INTERSECTION CENTER-LINE OF GRAVEL ROADS. CHECKED 1980 WITNESSES. C.M.P. IS STILL GOOD. T.P. HAS BEEN REPLACED WITH TELE. RISER. MEAS. EAST 5291.74' TO I-11, NORTH 5310.36' TO T-IRON IN ASPHALT ROAD, AND SOUTH 2627' TO CENTER ROAD OPPOSITE FENCES EAST AND WEST. COULD NOT FIND G-10 OR EVIDENCE OF OCCUPATION. COULD NOT FIND F-11 SURVEYOR CAMPBELL DOES NOT HAVE ANY NOTES ON 1979 SURVEY. ACCEPTED IRON FOR POSITION OF CORNER.

Corner, G-11 was approved for remonumentation at a Peer Review Committee Meeting on 11-12 1996.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 3/4"x18" GAS PIPE WITH BRASS CAP STAMPED "MIDLAND CO. REMON. COR. P.S. 9433".
ACCEPTED AS BEST AVAILABLE EVIDENCE OF THE ACCEPTED POSITION OF THE CORNER.



Signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 12-19-96