

APPROVED LAND CORNER  
P.A. 345 OF 1990  
MIDLAND COUNTY

311

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

STATE OF MICHIGAN  
MIDLAND COUNTY  
REMONUMENTATION & FILED

20 DEC 96 2:07 P.M.

BEVERLY J THAYER  
REGISTER OF DEEDS

MIDLAND (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>14N</u> R <u>2W</u>	H-11
	T <u>    </u> R <u>    </u>	_____
	T <u>    </u> R <u>    </u>	_____
	T <u>    </u> R <u>    </u>	_____
2. Property Controlling In Section	S <u>    </u> T <u>    </u> R <u>    </u>	_____
	S <u>    </u> T <u>    </u> R <u>    </u>	_____
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	_____
	S <u>    </u> T <u>    </u> R <u>    </u>	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, PAUL B. LAPHAM, in a field survey on NOVEMBER 19 95 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1830 WRIGHT  
SET 1/4 POST  
WIT.-BEECH 10" N51°E 21 LKS  
HEMLOCK 6" S37°W 15 LKS

NO DATE GIBBS, C.S.R.  
SET POST FOR 1/4 COR.  
40.10' TO I-11

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

MEAS. 5291.74' FROM G-11 TO I-11. SET MID POINT & SEARCHED FOR CORNER. EXCAVATED INTO ORIGINAL SOIL ACROSS ROAD. DID NOT FIND ANY EVIDENCE AT CORNER. AN OLD FENCE HAS BEEN ROLLED UP SOUTH OF CORNER. AN OPEN CULTIVATED FIELD LIES WEST OF THE CORNER ON THE NORTH SIDE OF THE ROAD. SET CORNER AT S.P.M. WHICH AGREES WITH C.S.R. I.E. 2645.87' MEAS. VS. 2646.6' C.S.R. AND LIES 2 FEET NORTH OF CENTERLINE OF ROAD.

Corner, H-11 was approved for remonumentation at a Peer Review Committee Meeting on 11-12, 1996.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 3/4"x18" GAS PIPE WITH BRASS CAP STAMPED "MIDLAND CO. REMON. COR. P.S. 9433"  
ACCEPTED AS BEST AVAILABLE EVIDENCE OF THE ACCEPTED POSITION OF THE CORNER.

WITNESSES:  
N57°E, 82.40' - NAIL & TAG IN 6" MAPLE  
S41°E, 67.58' - NAIL & TAG IN 11" RED OAK  
S18°E, 84.94' - NAIL & TAG IN 17" MAPLE  
S50°W, 56.88' - NAIL & TAG IN 7" SCOTCH PINE



Signed by Mark R. Robison  
Surveyor's Michigan License No. 27458

Date 12-19-96