

APPROVED LAND CORNER
P.A. 345 OF 1990
MIDLAND COUNTY

295

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

9/12/96 *[Signature]*

For corners in

Located In:	Corner Code #
MIDLAND (County)	1-10
1. Public Land Survey	T 14N R 2W
	T R
	T R
	T R
	T R
2. Property Controlling in Section	S T R
	S T R
3. Miscellaneous Property in Sec.	S T R
	S T R

STATE OF MICHIGAN
MIDLAND COUNTY
REMONUMENTATION & FILED

27 NOV 96 2:56 P.M.

BEVERLY J THAYER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, PAUL B. LAPHAM, in a field survey on NOVEMBER 19 95 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1830 WRIGHT SET 1/4 SEC. POST WIT.-SUGAR 14" N34°E 14 LKS. MAPLE 14" S34°W 44 LKS.	3-31-92 JONES, (132) 4-884 FOUND 3/8" ROD WIT.-S05°W, 39.40' - NAIL & TAG IN END G.R. POST S30°E, 51.05' - NAIL & TAG IN END G.R. POST SOUTH, 76.92' N. EDGE BRIDGE DECK N45°W, 45.89' - NAIL & TAG IN 12" PINE
---	--

NO DATE GIBBS
STONE FOR CORNER
39.83 TO I-9, 39.87 (?) TO I-11

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/8"x18" RE-ROD IN 3/4"x30" PIPE IN CENTER-LINE OF N-S ROAD AND 2' NORTH OF CENTERLINE OF ROAD EAST. FOUND & CHECKED ALL 1992 WITNESSES. MEASURED SOUTH 2630.20' (CSR 2631.42') TO I-11 AND NORTH 2634.54' (CSR 2628.78') TO I-9 ROAD HAS BEEN FILLED APPROXIMATELY 10 FEET ABOVE ORIGINAL GROUND.

Corner, I-10 was approved for remonumentation at a Peer Review Committee Meeting on SEP 12, 1996

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 3/4"x18" GAS PIPE WITH BRASS CAP STAMPED "MIDLAND CO. REMON. COR. P.S. 9433".
ACCEPTED AS BEST AVAILABLE EVIDENCE OF THE ACCEPTED POSITION OF THE CORNER.

WITNESSES:
N45°W, 72.18' - NAIL & TAG IN 23" W. PINE
S86°W, 68.50' - NAIL & TAG IN 26" ASH
N32°E, 167.84' - NAIL & TAG IN 17" SCOTCH PINE
S47°E, 117.20' - NAIL & TAG IN 13" TWIN ASH



Signed by *Paul B. Lapham*
Surveyor's Michigan License No. 9433

Date 10-09-96