

APPROVED LAND CORNER
P.A. 345 OF 1990
MIDLAND COUNTY

9/12/96 959

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

296

For corners in

| MIDLAND (County) | Located In: | Corner Code # |
|---------------------------------------|-------------------------------------------|---------------|
| 1. Public Land Survey | T <u>14N</u> R <u>2W</u> | <u>I-11</u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |

STATE OF MICHIGAN
MIDLAND COUNTY
REMONUMENTATION & FILED

27 NOV 96 2:56 P.M.

BEVERLY J THAYER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, PAUL B. LAPHAM, in a field survey on NOVEMBER 19 95 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | |
|----|---|----|---|----|---|----|---|----|---|----|---|----|
| 1 | A | B | C | D | E | F | G | H | I | J | K | L |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 |
| 3 | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 |
| 5 | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 |
| 7 | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 |
| 9 | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 |
| 11 | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 |
| 13 | | | | | | | | | | | | |

- A. Description of original monument and accessories and/or subsequent restoration:
- 1830 WRIGHT SET POST WIT.-SWP. OAK 20" S60°E 15 LKS. ELM 15" N4°W 50 LKS.
 - NO DATE GIBBS, C.S.R. SET NEW POST IN PLACE OF OLD POST 39.87' (?) TO I-10, 40.10' TO H-11
 - 12-18-80 MUELLER L.C.R.C. 535 FOUND SOLID ROD WIT.-N.E., 67.85' - 6" RED OAK S.E., 53.85' - CENTER-LINE EAST END 12" PIPE S.W. 54.1' - CENTER-LINE WEST END 12" PIPE N.W. 57.8' - PIPELINE MARKER
 - 5-17-92 BLANCHARD, (132) 5-13 FOUND IRON

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- FOUND 1/2"x36" SOLID ROD IN CENTER-LINE OF ROAD INTERSECTION. FOUND ONE 1980 WITNESS MEAS. NORTH 2630.20' (CSR 2631.42') TO I-10. MEAS. WEST 2645.87' (C.S.R. 2646.6') TO H-11.

Corner, I-11 was approved for remonumentation at a Peer Review Committee Meeting on SEP 12, 1996

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 3/4"x18" GAS PIPE WITH BRASS CAP STAMPED "MIDLAND CO. REMON. COR. P.S. 9433". ACCEPTED AS BEST AVAILABLE EVIDENCE OF THE ACCEPTED POSITION OF THE CORNER.

WITNESSES:
N51°E, 111.96' - NAIL & TAG IN 24" WHITE OAK
N53°E, 67.85' - NAIL & TAG IN 16" RED OAK (OBT)
S33°E, 116.03' - NAIL & TAG IN 13" RED OAK
S53°W, 94.08' - NAIL & TAG IN 13" WHITE OAK
N58°W, 111.41' NAIL & TAG IN 30" TWIN WHITE OAK



Signed by Paul B. Lapham
Surveyor's Michigan License No. 9433

Date 10-9-96