

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

REMONUMENTATION

Midland County Located In: Corner Code #

- 1. Public Land Survey T14N R2W J-3, J-5
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

33

STATE OF MICHIGAN  
HIGHLAND COUNTY  
REMONUMENTATION & FILED

30 NOV 93 3:12 P.M.

BEVERLY J THAYER  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

I, Norman C. Caldwell, in a field survey on May 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 2-13. Two black dots are marked at grid intersections (I, 3) and (I, 5).

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(J-3) 1/4 Cor., Sec. 2 & 11, T14N-R2W

Wood Post Placed by Joel Whight in 1832 Sub. of Twp.: S23°W 5 L. (1.006M) 18" (45cm) Pine; N23°E 15 L. (3.018M) 24" (61cm) Pine.

No Subsequent Record

(J-5) 1/4 Cor., Sec. 11 & 14, T14N-R2W

Wood Post Placed by Joel Whight in 1832 Sub. of Twp.: N50°E 19 L. (3.822M) 10" (25cm) Pine; S50°W 16 L. (3.219M) 10" (25cm) Black Ash.

L.C.R.C. by J. Jones, Recorded in Bk. 1 P. 573, Set 13mm Rod w/cap Equidistant on Line b/w I-5 & K-5 as recorded: South 25.061M 13cm Bar; SW 8.14M 26mm Pine; S1°W 13.740M Fnc Cor. Post; North 9.17M CL M-20. Survey by Jones, L. 3, pg. 407 & 409

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J-3) 1/4 Cor., Sec. 2 & 11, T14N-R2W

Placed 13mm x 45cm rebar w/cap #12018 from remains of original bearing trees.

(J-5) 1/4 Cor., Sec. 11 & 14, T14N-R2W

Found 13mm Rerod w/illegible cap per Bk.1 P. 573.



C. Description of monument for corner and accessories established to perpetuate, locating the position of the corner:

(J-3) 1/4 Cor., Sec. 2 & 11, T14N-R2W

Placed 13mm X 45cm Rebar w/cap #12018 from remains of original bearing trees and is accepted as a careful and faithful perpetuation of the position of the original corner.

- S13°W 5 L. (1.006M) 66cm Pine Stumpw/Pitch Face(Orig)
N14°E 15 L. (3.018M) Remains of 61cm Pine Stump(Orig)
N56°W 1.093M 12cm Maple
S60°W 3.676M 35cm Maple
S72°E 13.900M 35cm Maple
N44°E 4.237M 15cm Maple

(J-5) 1/4 Cor., Sec. 11 & 14, T14N-R2W

Found 13mm Re Rod(illegible cap) per Book 1, Page 573 and is accepted as a careful and faithful reestablishment of the position of the original corner.

- S01°W 13.800M Fence Cor Post (S&W)(R)
S05°W 24.478M 45.5cm White Oak
S68°W 26.810M 7.8cm Scotch Pine
N15°E 34.240M 30.5cm Red Pine
North 9.361M CL M-20

Signed by [Signature]

Date 24 NOV 93

Surveyor's Michigan License No. 12018