

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
REMONUMENTATION

STATE OF MICHIGAN
HIGHLAND COUNTY
REMONUMENTATION & FILED

37

For corners in

Midland	Located In:	Corner Code #
County		
1. Public Land Survey	T 14N R 2W	L-5/L-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

30 NOV 93 3:13 P.M.

BEVERLY J THAYER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Norman C. Caldwell, in a field survey on May, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	I
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(L-5) 1/4 Cor., Sec. 12 & 13, T14N-R2W

Wood Post Placed by Joel Whight in 1832 Sub. of Twp: N23°E 37 L.(7.443M) 16" (40cm) Pine; S23°W 24 L.(4.828M) 18" (45cm) Pine.

No Subsequent Record.

(L-7) 1/4 Cor., Sec. 13 & 24, T14N-R2W

Wood Post Placed by Joel Whight in 1832 Sub. of Twp: S53°E 15 L.(3.018M) 8" (20cm) Birch; N53°W 18 L.(3.621M) 16" (40cm) Aspen.

L.C.R.C. by P. Lapham, Recorded in Bk. 1 P. 330, Found 26mm Pipe: N15°W 13.046M 61cm W. Oak; S75°W 26.643M P. Pole; South 17.319M 25.5cm Oak.

L.C.R.C. by H. Fluharty, Recorded in Bk. 1 P. 602, Found 13mm Rerod on CL Rd.: N15°W 13.046M 61cm W. Oak; S15°W 17.4:2 30.5cm Oak; S75°W 26.643M P.P.

Survey by MacDonald, L. 3, pg. 672

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(L-5) 1/4 Cor., Sec. 12 & 13, T14N-R2W

Placed 13mm x 45cm Rebar w/cap #12018 in Mon. Box in paved shoulder by Single Proportion at Midpoint and on line b/w acceptable Section Corners.

(L-7) 1/4 Cor., Sec. 13 & 24, T14N-R2W

Found 26mm Pipe w/cap per Bk. 1 Pgs. 330 & 602.



C. Description of monument for corner and accessories established to locate the position of the corner:

(L-5) 1/4 Cor., Sec. 12 & 13, T14N-R2W

Placed 13mm X 45cm Rebar w/cap#12018 in Mon Box, in paved shoulder and is accepted as a careful and faithful reestablishment of the position of the original corner.

S82°W 26.780M 25 Scotch Pine
S65°W 20.063M 12cm
S28°W 26.172M 38cm White Oak
S45°E 18.145M 10cm Ash
North 8.58 C/L pavement

(L-7) 1/4 Cor., Sec. 13 & 24, T14N-R2W

Found 26mm Pipe w/cap per Book 1, Page 330 & 602, and is accepted as the best available evidence of the position of the original corner.

N17°W 13.025M 66cm White Oak(R)
S15°W 17.411M 30cm White Oak(R)
South 10.044M 10cm Pipe (C/L West Side)
S36°E 42.750M 25cm Quad Black Oak

Signed by Norman C. Caldwell

Date 29 Nov 93

Surveyor's Michigan License No. 12018