

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>15</u> N. <u>0.</u> , R. <u>1</u> W. <u>0.</u>	I-1, I-2, I-3
2. PROPERTY CONTROL- ING IN SECTION _____	T. _____ N. _____ S., R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S., R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, CARL ROSER, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on JANUARY 10, 1986, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- I-1 FD. & ACCEPTED 3/4" SOLID IRON ROD BY R.L.S. PAUL LAPHAM FOR SEC.COR. COMM. TO SEC'S 34 & 35 (T16N-R1W) & SEC'S 2 & 3 (T15N-R1W).
- I-2 RE-ESTABLISHED W 1/4 CORNER OF SEC.2 ON LINE BETWEEN THE NW & SW CORNERS OF SEC.2 & @ PRORATED DISTANCE TO U.S. (G.L.O.) SURVEY. CTR. OF N-S MUD TRAIL IS WEST 20' ±.
- I-3 FD. & ACCEPTED 3/4" PIPE FOR SW CORNER OF SEC.2. CTR. OF E-W DIRT TRAIL ROAD IS 6' ± SOUTH. CTR. OF N-S MUD TRAIL ROAD TO NORTH IS 18' ± WEST. COR. IS IN LINE WITH TRAIL RD LOOKING SOUTH.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-1	I-2	I-3
FD 3/4" SOLID IRON ROD	SET DNR MON & CEDAR POST	FD 3/4" PIPE
P. POLE N60°W 43.28'	7" TWIN MAPLE N74°E 1.0'	DROVE 5/8" X 6" REROD W/RLS
11"MAPLE S36°W 117.78'	10" MAPLE S28°E 6.3'	CAP INSIDE
4"MAPLE S50°E 63.32'	12" OAK N60°W 43.6'	10" MAPLE N70°E 14.83'
8"OAK S20°W 103.00'	12" MAPLE N40°E 26.2'	10" TRI MAPLE S42°E 46.66'
SET CEDAR POST		26" OAK(CLUMP)S72°W 79.58'
W/LOC TAG SOUTH 30'		30" OAK N68°W 65.44'
		SET CEDAR POST
		W/LOC TAG SOUTH 20'

SIGNED BY Carl F. Roser 01-17-86 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

JEROME TOWNSHIP
MIDLAND COUNTY

SURVEYOR'S MICHIGAN REGISTRATION NO. _____