

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF--: | LOCATED IN--: | CORNER CODE NUMBER |
|---|--|--------------------|
| 1. PUBLIC LAND SURVEY _____ | T. <u>15</u> N. <u>1</u> E. <u>1</u> S. <u>1</u> W. _____ | <u>J-3</u> |
| 2. PROPERTY CONTROLLING IN SECTION <u>2</u> | T. <u>15</u> N. <u>1</u> E. <u>1</u> S. <u>1</u> W. _____ | <u>12, 15</u> |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ | T. _____ N. _____ E. _____ S. _____ W. _____ | _____ |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, CARL ROSER, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on JANUARY 10, 1986, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- J-3 FD. AND ACCEPTED 3/4" PIPE FOR S 1/4 CORNER OF SEC.2. COR FITS WITS ON RECORD AT MIDLAND CO. REG OF DEEDS; R.L.S., J. SCHAFER.
- 12 DROVE 5/8" X 34" REROD FOR SE CORNER OF NE 1/4 OF SW1/4 OF SEC.2.
- 15 DROVE 5/8" X 34" REROD FOR SE CORNER OF SW 1/4 OF SW1/4 OF SEC.2. CORNER FALLS AT NORTH EDGE OF E-W SAND ROAD.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| | J-3 | 12 | 15 |
|---|-----|--|-----------------------------------|
| FD 3/4" PIPE 0.2'± BELOW B. TOP; RAISED W/3/8" CABIN SPIKE. | | DROVE 5/8" X 34" REROD W/RLS CAP AND SET CED. POST W/LOC. TAG. | DROVE 5/8" X 34" REROD W/RLS CAP. |
| 31" PINE S14°E 57.21' | | 6" TWIN MAPLE N66°W 12.41' | 20" TWIN MAPLE N04°E 54.84' |
| P. POLE S22°W 95.50' | | 5" MAPLE S52°W 24.16' | 24" OAK S04°E 31.48' |
| 18" OAK S50°E 60.66' | | 6" MAPLE S42°E 18.94' | 6" MAPLE N64°W 13.92' |
| 28" PINE N04°E 46.42' | | FD. 3/4" PIPE | SET CEDAR POST |
| SET CEDAR POST W/LOC TAG SOUTH 33' | | W/RLS CAP#16409 N 0°33'W 3.10' | W/LOC TAG NORTH 33' |

SIGNED BY Carl F. Roser 01-17-86 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____



(SEAL)
JEROME TOWNSHIP
MIDLAND COUNTY

SURVEYOR'S MICHIGAN REGISTRATION NO. _____