

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. 15 N. 1 W.	15 N. 1 W.	J-1, J-2
2. PROPERTY CONTROLLING IN SECTION 2, T. 15 N. 1 W.	15 N. 1 W.	1, 11
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, CARL ROSER, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on JANUARY 10, 1986, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

XX

B. CONTINUED:

11 DROVE 5/8" X 34" REROD FOR CTR. OF SW 1/4 OF SEC.2.

C. CONTINUED:

11

DROVE 5/8" X 34" REROD W/RLS CAP & SET CEDAR POST W/LOC TAG.

12" MAPLE	N32°W	25.75'
17" TWIN OAK	N34°E	20.31'
14" OAK	S66°E	21.35'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

J-1 FD & ACCEPTED 3/8" REROD FOR N1/4 COR. SEC.2. CORNER PREVIOUSLY ACCEPTED AS S1/4 COR. OF SEC. 35, T16N-R1W BY R.L.S., PAUL LAPHAM.

J-2 FD & ACCEPTED 1/2" REROD W/ORANGE PLASTIC R.L.S. CAP (R.L.MERRY, #19790) FOR CTR. OF SEC.2. COR. FALLS IN OLD (DOWN) FN. REMAINS N-S-E- @ OLD COR. FN. POST (DOWN-IN LEATHER-LEAF & WILLOW BRUSH BOG). KEITH FRANCIS (OLD TIMER) WHOSE PARENTS LIVED HERE BEFORE HIM SAID THERE WAS A REAL OLD FENCE (THAT HE HAD NOT SEEN IN SOME TIME) IN THE BOG WHERE WE FOUND THE OLD COR. POST DOWN WITH 1/2" ROD BY SAME.

1 DROVE 5/8" REROD FOR W1/8 COR. ON N. LINE OF SEC.2; MID-WAY & ON LINE BETWEEN SEC.COR. TO W & 1/4 COR. TO E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-1	J-2	1
FD. 3/8" REROD IN B. TOP RD.	FD. 1/2" REROD AT FN COR., SET	DROVE 5/8"X18" REROD
* 48" OAK N30°W 38.19'	CED POST W/LOC TAG	W/RLS CAP
* 40" OAK N72°W 73.45'	16" MAPLE IN CLUMP N22°E 57.67'	:: 9" OAK N14°W 38.55'
* P. POLE S50°W 51.11'	5" W.PINE S12°W 17.29'	* 20" OAK N40°E 64.55'
14" OAK S10°E 40.28'	12" OAK S62°W 36.42'	18" OAK S40W 54.24
	12" R.PINE N22°W 34.35	CTR. E-W B. TOP RD.
		SOUTH 8.5±

* OLDER WITS PER P.LAPHAM
CERT. OF SURVEY

* FD. DNR REF. TAG & NAIL

SIGNED BY Carl F. Roser 01-17-86 DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

JEROME TOWNSHIP
MIDLAND COUNTY