

**MIDLAND COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. PA 1970

<u>Midland</u> (County)	Located In	Corner Code #
1. Public Land Survey	T <u>15N</u> R <u>1W</u>	<u>B11</u>
2. Property Controlling in Section	T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on Oct. 3, 2011 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- B11 – 1852 – GLO – A. Burt – Set ¼ Post
- 1) Tamarack 12" S17°W 32 L.
 - 2) W. Pine 10' N22°W 33 L.
- 1919 – CSR – L. 1, p. 401 – F. J. Gibbs.
Set Gas pipe at average distance on true line.
- 1971 – Lapham & Assoc., Gas pipe 29' South of fence.
3) N 29.0' post; 4) N45°E 17.4' – 24" Oak; 5) S45°E 40.0' – 24" Oak
- 1977 – Rec. Survey – L. 2, p. 432 & Notes – J. A. Schafer –
Fd. 1 ½" pipe

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

B11 – ¼ Corner common to Sections 30 & 31, T15N, R1W – Fd. 1 ¼" I.D. x 1.5' long iron pipe in N-S fence remains. No GLO evidence. Pipe fits Gibbs, Lapham & Schafer surveys in area. 1 ¼" iron pipe accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B11 – Replaced 1 ¼" x 1.5' long iron pipe with Stamped 4" DNR Aluminum Cap on 1" x 36" long galv. iron pipe.
Place 1 ¼" pipe at base of DNR monument as memorial.
Set Blue Carsonite Post 1' North.
N4°E 66.10' to set Nail and Tag (N & T) in W. side 13" Oak scribed 'XBT'
N66°E 50.27' to set N & T in S. side 17" W. Oak scribed 'XBT'
S19°E 32.81' to set N & T in E. side 12" Red Maple
N56°W 28.75' to set N & T in NE side 14" Red Maple scribed 'XBT'



Signed by: Craig W. McVean
Surveyor's Michigan License No.: 39088

Date: 10/15/2012