

REMON. COR. M-3, GENEVA TWP.
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Midland
(County)

- | | | |
|---------------------------------------|--------------------------|--------------|
| 1. Public Land Survey | T <u>15N</u> R <u>2W</u> | <u>M-3</u> |
| | T <u>15N</u> R <u>1W</u> | <u>A-3</u> ✓ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

STATE OF MICHIGAN
MIDLAND COUNTY
REMONUMENTATION & FILED
12/15/1999 8:26:43 AM
SCOTT I. HAINES
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, **RODNEY CLAYPOOL**, in a field survey on **June 18, 1998**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

M-3, A-3 Corner common to Sections 1, 12 T15N-R2W and 6, 7 T15N-R1W
Survey by Glo 1830's, set post
Survey of N. Buttonville, 1874
Survey by MDOT, 1931, found
Survey by H. Gilbert, 1983
Survey by P. Lapham, 1986, 1987, found monument box
LCRC by P. Lapham, 1986, monument box

SURVEY &
REMONUMENTATION

FEB 09 2000

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-3, A-3 Corner common to Sections 1, 12 T15N-R2W and 6, 7 T15N-R1W
Found iron pin in monument box per surveys by MDOT, H. Gilbert, P. Lapham and LCRC by P. Lapham.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-3, A-3 Corner common to Sections 1, 12 T15N-R2W and 6, 7 T15N-R1W
Replaced pin with 5/8" rod and brass cap stamped Midland Co. Remon Cor PS 29241 and is accepted as the best available evidence of the position of the accepted corner.
S 63 Deg E, 79.7', centerline 36" Walnut
S 40 Deg E, 102.65', NW corner house
S 88 Deg W, 62.09', nail in power pole
N 35 Deg W, 110.57', nail in twin 15" Pine

Signed by Rodney D. Claypool
Surveyor's Michigan License No. 29241

Date 12-11-99

Form approved by Michigan State Board of Land Surveyors, Jan. 28, 1971
Revised May 14, 1971
Revised Jan., 1983

RECORDED LAND CORNER
P.A. 345 OF 1970
MIDLAND COUNTY

9/12/1999

