

**REMON. COR. M-4, GENEVA TWP.
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

467

For corners in
Midland
(County)

Located in: Corner Code #

- | | | |
|------------------------------------|--------------------------|--------------|
| 1. Public Land Survey | T <u>15N</u> R <u>2W</u> | <u>M-4</u> |
| | T <u>15NR</u> <u>1W</u> | <u>A-4</u> ✓ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

STATE OF MICHIGAN
MIDLAND COUNTY
REMONUMENTATION & FILED

12/15/1999 8:26:43 AM

SCOTT I. HAINES
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, RODNEY CLAYPOOL, in a field survey on June 18, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

A. Description of original monument and accessories and/or subsequent restoration:

- M-4 ¼ Corner common to Section 12, T15N-R2W and Section 7, T15N-R1W
A-4
Survey by Glo, 1830, set post
Survey by F. Gibbs, 1906, set iron grate
Survey by M. Hunter, 1968, found iron grate
Survey by D. Whittier, 1972, found stove grate
Survey by H. Gilbert 1994, found ½" x 3" bar, 3' deep raised with ½" rod and cap

SURVEY &
REMONUMENTATION

FEB 09 2000

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-4 ¼ Corner common to Section 12, T15N-R2W and Section 7, T15N-R1W
A-4
Found rod & cap #22433 per surveys by F. Gibbs, M. Hunter, D. Whittier and H. Gilbert.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-4 ¼ Corner common to Section 12, T15N-R2W and Section 7, T15N-R1W
A-4
Replaced ½" rod & cap with 5/8" rod and brass cap stamped Midland Co. Remon Cor PS 29241 and is accepted as the best availat evidence of the position of the accepted corner.
S 30 Deg E, 64.45, nail and disc in power pole (Rec.)
N 75 Deg E, 36.90, nail and disc in 10" Ash (Rec.)
N 40 Deg E, 47.35, nail and disc in 8" Ash (Rec.)
S 10 Deg W, 77.89, nail and disc in guard rail post (Rec.)

Signed by Rodney D. Claypool
Surveyor's Michigan License No. 29241

Date 12-11-99

Form approved by Michigan State Board of Land Surveyors, Jan. 28, 1971
Revised May 14, 1971
Revised Jan., 1983

MIDLAND COUNTY
PLAT 315 OF 1500
MIDLAND COUNTY

9/12/99 JG

