

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
MIDLAND COUNTY  
REMONUMENTATION & FILED

14 AUG 95 3:02 P.M.

BEVERLY J THAYER  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

MIDLAND (County)	Located In:	Corner Code #
1. Public Land Survey	T15N R1W	A-6
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, PAUL B. LAPHAM, in a field survey on MAY, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-6: West 1/4 Corner Section 18, *CORNER COMMON TO M-6, T15N-R2W*

1830 CLARK T15N, R2W, ELM 15" S1°E 37 LKS., MAPLE 17" N26°W, 32 LKS.

NO C.S.R.

4-27-90 LEDY. FOUND 1/2" ROD

WITNESS NOTE: Witnesses from above surveys and LCRC's are available in dossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-6: West 1/4 Corner Section 18

Found 1/2" rod and witnesses per Ledy Survey at intersection of gravel roads. Measured North 2633.5' to A-5.

SURVEY &  
REMONUMENTATION

NOV 14 1995

COMMISSION

Corner, A-6 was approved for remonumentation at a Peer Review Committee Meeting on 7-18, 19 95.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-6: West 1/4 Corner Section 18

Set 5/8" x 18" re-rod with brass cap stamped "Midland Co. Remon. Cor. PS 9433" in gravel road Accepted as best available evidence of the accepted position of the corner.

S42°E 43.47' - N&T IN CENTER FENCE POST  
N43°E 60.66' - N&T IN 10" W. PINE  
N40°W 77.27' - N&T IN POWER POLE  
S77°W 41.05' - N&T IN 8" OAK



Signed by Paul B. Lapham  
Surveyor's Michigan License No. 9433

Date 7/21/95