

SURVEY & REMONUMENTATION

FEB 09 2000

**REMON. COR. M-12, GENEVA TWP.
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

468

SECTION
For corners in Midland
(County)

- | | | |
|---------------------------------------|--------------------------|--------------|
| 1. Public Land Survey | T <u>15N</u> R <u>2W</u> | _____ M-12 |
| | T <u>15N</u> R <u>1W</u> | _____ A-12 ✓ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

STATE OF MICHIGAN
MIDLAND COUNTY
REMONUMENTATION & FILED

12/15/1999 8:26:43 AM

SCOTT I. HAINES
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, RODNEY CLAYPOOL, in a field survey on June 18, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below;

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

M-12, A-12 ¼ Corner common to Sections 36, T15N-R2W and 31, T15N-R1W

Survey by Glo, 1830's, set wood post
Survey by J. Schafer, 1977, found wood stake, set ¾" rod 3' long.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-12, A-12 ¼ Corner common to Sections 36, T15N-R2W and 31, T15N-R1W

Found ¾" rod per survey by J. Schafer.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-12, A-12 ¼ Corner common to Sections 36, T15N-R2W and 31, T15N-R1W

Replaced ¾" rod with ¾" pipe and brass cap stamped Midland Co. Remon Cor PS 29241, in monument box, and is accepted as the best available evidence of the position of the original corner.

N 70 Deg W, 52.40, nail and plastic disc in power pole
West 41.00, nail and plastic disc in 24" Oak (Rec.)
S 60 Deg W, 40.40, nail and plastic disc in 18" Willow (Rec.)
S 25 Deg E, 67.81, nail and plastic disc in power pole
N 70 Deg E, 69.14, nail and plastic disc in power pole

Signed by Rodney D. Claypool
Surveyor's Michigan License No. 29241

Date 12-11-99

Form approved by Michigan State Board of Land Surveyors, Jan. 28, 1971
Revised May 14, 1971
Revised Jan., 1983

MIDLAND COUNTY
P.A. 645 OF 1970
MIDLAND COUNTY

9/17/99

