

BBB 5/18/95

MIDLAND COUNTY  
P.A. 345 OF 1990  
APPROVED LAND CORNER

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

237

For corners in

MIDLAND (County)	Located In:	Corner Code #
1. Public Land Survey	T 15N R 1W	C-6
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
MIDLAND COUNTY  
REMONUMENTATION & FILED

14 AUG 95 3:03 P.M.

BEVERLY J THAYER  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, PAUL B. LAPHAM, in a field survey on MAY, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-6: 1/4 Corner common to Sections 17 & 18

1852 AUSTIN BURT, POST, W. ASH 18" S30°E 14 LKS., W. PINE 8" N80°W, 18 LKS.

NO C.S.R.

10-20-78 PAUL LAPHAM, FOUND 3/4" BAR L.C.R.C.

4-27-90 LEDY, FOUND 3/4" ROD (132) SURVEY

WITNESS NOTE: Witnesses from above surveys and LCRC's are available in dossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-6: 1/4 Corner common to Sections 17 & 18

Found 3/4"x18" rod per surveys by Lapham and Ledy. Meas. South 2633.58' to C-7 and North 2627.33' to C-5.

SURVEY &  
REMONUMENTATION

NO. 9433

CORNER

Corner, C-6 was approved for remonumentation at a Peer Review Committee Meeting on 7-18, 19 95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-6: 1/4 Corner common to Sections 17 & 18

Set 5/8" x 18" re-rod with brass cap stamped "Midland Co. Remon. Cor. PS 9433" in Monument Box per Surveys by Lapham & Ledy. Accepted as best available evidence of the accepted position of the corner.

N45°E 65.59' TO N&T IN POWER POLE  
N60°E 31.28' TO Q FIRE HYD.  
S45°E 38.3' - PHONE RISER  
N30°W 135.0' - SE CORNER OF HOUSE



Signed by Paul B. Lapham

Date 2-19-95

Surveyor's Michigan License No. 9433