

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
MIDLAND COUNTY
REMONUMENTATION & FILED

14 AUG 95 3:03 P.M.

BEVERLY J THAYER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

MIDLAND (County)	Located In:	Corner Code #
1. Public Land Survey	T15N R1W	C-7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, PAUL B. LAPHAM, in a field survey on MAY, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- C-7 Corner common to Sections 17, 18, 19 and 20
- 1852 AUSTIN BURT, SET TEMPY, POST DID NOT WITNESS
- 9-20-78 PAUL LAPHAM, SET 1/2" CAPPED RE-ROD L.C.R.C.
- 6-25-90 MARK ROBISON, FOUND 1/2" CAPPED RE-ROD (132) SURVEY

WITNESS NOTE: Witness from above surveys and LCRC's are available in dossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- C-7 Corner common to Sections 17, 18, 19 and 20
- Found 1/2"X18" C.I. in seal coat asphalt road per Lapham and Robison Surveys. Measured 2627.33' North to C-6 and 5285.60 feet South to C-9.

SURVEY'S
REMONUMENTATION
JUL 1995
C.M.P.

Corner, C-7 was approved for remonumentation at a Peer Review Committee Meeting on 7-18, 1995.
Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-7 Corner common to Sections 17, 18, 19 and 20
- Set 5/8" x 18" re-rod with brass cap stamped "Midland Co. Remon. Cor. PS 9433" in Monument Box per surveys by Lapham and Robison. Accepted as best available evidence of the accepted position of the corner.

- S85°W 33.20' - N&T IN CORNER POST
- N50°E 54.88' - N&T IN POWER POLE
- S20°E 86.0' - FIRE HYD.
- S35°W 36.15' - WEST END 30" C.M.P.



igned by Paul B. Lapham
urveyor's Michigan License No. 9433

Date 7/21/95