

APPROVED LAND CORNER  
P.A. 345 OF 1990  
MIDLAND COUNTY

MIDLAND COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

361

For corners in

MIDLAND  
(County)

Located In:

Corner Code #

1. Public Land Survey

T 15N R 1W

C-13 ✓

T 14N R 1W

C-1

T R

T R

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
MIDLAND COUNTY  
FILED &  
REMONUMENTATION  
11 DEC 97 12:03 P.M.

BEVERLY J THAYER  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, MARK R. ROBISON, in a field survey on July 1, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

SURVEY &  
REMONUMENTATION

FEB 24 1998

SECTION

A. Description of original monument and accessories and/or subsequent restoration:

1830 Clark  
Wit-Pine 16 N24E, 11 lks.  
Hemlock 14 N75W, 21 lks.

4-10-73 Schafer, L.C.R.C. 224  
Fd 3/4" Pipe  
Wit.-N60W 93.50 Tag in P.P.  
S50W 57.72 N.E. Cor. Hse

7-11-19 Gibbs, C.S.R.  
Set Pine root Post for Corner  
North 39.92 to C-12  
West 39.92 to B-13

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" x 18" pinch pipe in asphalt pvm't. Found old P.P. witness. House is gone. Excavated to 30"; found no other evidence. Measured North 2632.36 (C.S.R. 2634.72) to old C.S.R. corner (pump casting) at C-12.

Corners, C-13, T15N, R1W, & C-1, T14N, R1W, were approved for remonumentation at a Peer Review Committee Meeting on August 1, 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 18" Gas Pipe with Brass Cap stamped "Midland Co. Remon. Cor. P.S. 27458" in Monument Box. Accepted as best available evidence of the accepted position of the corner.

Witnesses:

N88E 78.16', nail & tag, 12" Oak  
S37E 53.12', nail & tag, 10" W. Pine  
S40W 48.32', nail & tag, 30" Elm  
N68W 93.40', nail & tag, P.P. (OBT)

Signed by Mark R. Robison  
Surveyor's Michigan License No. 27458

Date 10-31-97

