

APPROVED LAND CORNER
P.A. 345 OF 1990
MIDLAND COUNTY

MIDLAND COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

8/01/97

For corners in

MIDLAND

(County)

Located In:

Corner Code #

- | | | | |
|------------------------------------|---------|--------------------------|-------------|
| 1. Public Land Survey | | T <u>15N</u> R <u>1W</u> | <u>E-12</u> |
| | | T _____ R _____ | _____ |
| | | T _____ R _____ | _____ |
| | | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ | T _____ R _____ | _____ |
| | S _____ | T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ | T _____ R _____ | _____ |
| | S _____ | T _____ R _____ | _____ |

362

STATE OF MICHIGAN
MIDLAND COUNTY
FILED
REMONUMENTATION
11 DEC 97 12:03 P.M.

BEVERLY J THAYER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, MARK R. ROBISON, in a field survey on July 1, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1852 Burt
Wit.-W. Birch 12 S68W 8 lks
Hemlock 6 N24E 21 lks

Undated Gibbs, C.S.R.
Wit.-same as above

Undated Gibbs, C.S.R.
Set Post w/ 4 brick around
North 40.21 to E-11
South 40.02 to E-13

9-18-81 Lapham, L.C.R.C. 546
Found 1" pipe
Wit.-S05E 29.65 Gate Post
S10W 32.60 Gate Post
S60E 25.13 Stud Pole
N45W 57.7 8" Pine

SURVEY &
REMONUMENTATION

FEB 24 1998

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" x 18" pipe. Excavated to 3.5 feet. Found 3/4" black plastic pipe (Gas?) running through bottom of hole indicating area has been disturbed. Found gate post and stump of 8" Pine witness. Measured North 2653.18 feet (C.S.R. 2653.86) to E-11.

Corner, E-12 was approved for remonumentation at a Peer Review Committee Meeting on 8-1-97, 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 18" Gas Pipe with Brass Cap stamped "Midland Co. Remon. Cor. P.S. 27458" in Monument Box. Accepted as best available evidence of the accepted position of the corner.

Witnesses:
S10W 32.60' Center of Stone Gate Post (OBT)
N55W 72.08', nail & tag, 12" W. Pine
N53E 67.40', nail & tag, P.P.
S58W 81.84,, nail & tag, 22" W. Pine

Signed by Mark Robison
Surveyor's Michigan License No. 27458

Date 10-31-97

