

REMONUMENTATION

APR 28 1995

APPROVED LAND CORNER
P.A. 345 OF 1990
MIDLAND COUNTY

COMMISSION

131

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in 1162/94 J.S.G.

MIDLAND (County)	Located In:	Corner Code #
1. Public Land Survey	T 15N R 1W	G-11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
MIDLAND COUNTY
REMONUMENTATION & FILED

8 NOV 94 9:23 A.M.

BEVERLY J THAYER
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K
2	6	5	4	3	2						
3											
4	7	8	9	10	11						
5											
6	18	17	16	15	14						
7											
8	19	20	21	22	23						
9											
10	30	29	28	27	26						
11											
12	31	32	33	34	35						
13											

I, PAUL B. LAPHAM, in a field survey on JULY, 19 94,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 G-11: Section Corner common to Sections 27, 28, 33 & 34.
 1852 - Austin Burt, W. Pine 14" S 52°E, 58 lks, W. Ash 7" N 29-1/2°W, 24 lks
 10/03/14 - Gibbs, Old Post well preserved C.S.R. Pg. 360-361
 03/25/83 - Harvey Gilbert, Found 3/4" Pipe L.C.R.C. #574
 (1) NW, 61.55' - Tele. Pole (2) SW, 48.93' - Power Pole
 (3) SE, 57.55' - Tele. Pole (4) NE, 47.14' - Street Sign
 03/14/83 - Harvey Gilbert 3/4" Pipe (132) 3-420 - Witnesses 1, 2, 3 & 4 as above.
 10/29/87 - Duane Ledy, Found 3/4" Pipe (132) 4-159 - Witnesses 1, 2 & 3 as above.
 (5) NE, 61.55' - Tele. Pole
 05/07/92 - Jerry Jones, Found 3/4" Pipe (132) 4-889
 (6) N 45°E, 49.61' - PK Nail in Guy Pole (7) S 45°W, 77.48' - Nail & Disk in Power Pole
 (8) S 50°E, 61.79' - PK Nail in Tele. Pole Stub
 02/10/93 - Duane Ledy, Found 3/4" Pipe (132) 4-967 - Witnesses 1, 2, 3 & 5 as above.
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 G-11: Section Corner common to Sections 27, 28, 33 & 34.
 Found 3/4" x 18" Pipe. Excavated to depth of 3 feet. Did not find further evidence.
 Found Recorded Witnesses 1, 2, 4, also (8) appears to be same as (1), except the bearing is
 reversed.

Accepted as best available evidence of the position of the original corner & replaced with Standard Monument.

Corner G-11 was approved for remonumentation at a Peer Review Committee Meeting on 11-02, 1994.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 G-11: Section Corner common to Sections 27, 28, 33 & 34.
 Set 5/8" x 36" re-rod with brass cap stamped "Midland Co. Remon. Cor. PS 9433"
 S 50°W, 49.5' - Power Pole (2)
 S 30°E, 56.85' - Tele. Pedestal
 N 51°E, 47.14' - Street Sign (4)
 N 58°E, 53.65' - Guy Pole
 N 58°W, 61.79' - Tele. Riser Post (1)



Signed by Paul B. Lapham Date 11-03-94
Surveyor's Michigan License No. 9433