

**SURVEY &  
REMONUMENTATION**

APR 28 1995

COMMISSION

156

**APPROVED LAND CORNER  
P.A. 345 OF 1990  
MIDLAND COUNTY**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
MIDLAND COUNTY  
REMONUMENTATION & FILED

11/28/94 JLG

For corners in

7 DEC 94 8:24 A.M.

<u>MIDLAND</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>15N</u> R <u>1W</u>	<u>K-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

BEVERLY J THAYER  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, PAUL B. LAPHAM, in a field survey on NOVEMBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2			
3												
4	7		8		9		10		11			
5												
6	18		17		16		15		14			
7												
8	19		20		21		22		23			
9												
10	30		29		28		27		26			
11												
12	31		32		33		34		35			
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

1852 AUSTIN BURT, PG. 143  
OLD CORNER-NO WITNESSES

NO C.S.R.

7-23-75 SCHAFER, L.C.R.C. #362  
FOUND 3/4" PIPE  
WIT.-(1) IN FLOW LINE OF WEST DITCH  
(2) WEST 9.0' TAG IN CLUMP OF 12" MAPLES  
(3) S5°W 46.5' TAG IN GUY POLE  
(4) S85°E 52.6' TAG IN TELE. POLE

3-30-81 JONES, PER REC. NO. 362. (132)-REC. 10-6-81

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

FOUND 3/4" PIPE IN FLOW LINE OF WEST DITCH.  
FOUND WITNESSES (1) (2) (3) & (4).

Accepted as best available evidence of the position of the original corner & replaced with Standard Monument.

Corner, K-7 was approved for remonumentation at a Peer Review Committee Meeting on 11-28, 19 94.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

K-7: Corner common to Sections 13, 14, 23 & 24  
SET 5/8"x36" re-rod with brass cap stamped "Midland Co. Remon. Cor. PS 9433"  
WEST 9.0' TAG IN MAPLE CLUMP(2)  
S5°W 45.6' TAG IN GUY POLE(3) REC. 46.5'  
S85°E 49.3' TAG IN TELE. POLE (NEW POLE)  
N45°E 67.6' TAG IN POWER POLE



Signed by Paul B. Lapham

Date Dec 1, 1994

Surveyor's Michigan License No. 9433