

JAN 21 1999

APPROVED LAND... P.A. 845 OF 1970 MIDLAND COUNTY

MIDLAND County Remonumentation SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

381

For corners in

Table with columns: MIDLAND (County), Located in:, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

STATE OF MICHIGAN MIDLAND COUNTY REMONUMENTATION & FILED

12/16/1998 12:11:56 PM

BEVERLY J. THAYER REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat 5. Private Claims

I, Mark R Robison, in a field survey on September, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

Grid table with columns A-M and rows 1-13. Contains numerical values from 1 to 36.

A. Description of original monument and accessories and/or subsequent restoration:

- List of monuments and accessories including: K-10: 1852 Burt 1/4 Sec Post, 12-6-77 Schafer (132) 2-446, 5-11-88 Ledy LCRC#649 Fd Mon Box, etc.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-10: Found 3/4" x 24" Iron Rod. At 4 feet depth found 1 1/2" x 16" Pipe. Found two 1973 witnesses and four 1988 witnesses. Measured 2642.53 (Jones 2642.39) feet North to Section Corner.

Corner, K-10, was approved for remonumentation at a Peer Review Committee Meeting on 11/24/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-10: Set 3/4" x 18" Gas Pipe with Brass Cap stamped "Midland Co. Remon. Cor. P.S.27458" in Monument Box. Accepted as best available evidence of the accepted position of the corner.

- Witnesses: S87W 57.34', nail & tag, Service Pole (OBT), N59E 30.67', nail & tag, Light Pole (OBT), S50E 97.58', nail & tag, Triple Oak (OBT), N37W 57.40', nail & tag, 22" Oak (OBT)



Signed by [Signature] Surveyor's Michigan License No. 27458

Date 12-09-12