

APPROVED LAND CORNER  
P.A. 345 OF 1990  
MIDLAND COUNTY

312

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
MIDLAND COUNTY  
REMONUMENTATION & FILED

11/12/96 grr

20 DEC 96 2:07 P.M.

BEVERLY J THAYER  
REGISTER OF DEEDS

For corners in

Located in:

Corner Code #

MIDLAND  
(County)

1. Public Land Survey

T15N R 1W

K-13 ✓

~~T14N R 1W~~

~~K-1~~

T R

T R

2. Property Controlling  
in Section

S T R

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, PAUL R. LAPHAM, in a field survey on NOVEMBER, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1852 BURT  
COR. OF SECS. 35-36  
WIT.-HEMLOCK 24" N51° 1/3E 60 LKS.  
W OAK 14" N63°W 12 LKS.

8-30-90 MACDONALD, (132) 4-686  
FOUND 1/2" REBAR  
WIT.-S75°E, 28.85' - NAIL IN 10" OAK  
N56°E, 30.45' - NAIL IN 8" MAPLE  
S74°W, 21.45' - NAIL IN 14" OAK  
S46°W, 53.45' - NAIL IN 12" MAPLE

1-7-77 LAPHAM, L.C.R.C.  
FOUND 3/4" PIPE  
WIT.-N45°E, 29.53' - 5" MAPLE  
S85°E, 29.52' - 8" RED OAK  
S45°W, 54.87' - 6" MAPLE  
EAST, FENCE

K-13, T15N-R1W IS COMMON  
WITH K-1, T14N-R1W

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2x36" IRON BAR (NOT 3/4" PIPE) APPROXIMATELY 1 1/2 FEET S.W. OF A SPIKE. NAIL FIT 1977 WITNESSES APPROXIMATELY, 1/2" BAR FIT 1990 WITNESSES. ACCEPTED 1/2" BAR AS CORNER, COMMON CORNER

Corner, K-13 <sup>AND K-1</sup> was approved for remonumentation at a Peer Review Committee Meeting on 11-12, 1996.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 3/4"x18" GAS PIPE WITH BRASS CAP STAMPED "MIDLAND CO. REMON. COR. P.S. 9433", ACCEPTED AS BEST AVAILABLE EVIDENCE OF THE ACCEPTED POSITION OF THE CORNER.

WITNESSES:  
N45°E, 30.48' - NAIL & TAG IN 8" MAPLE (OBT)  
S85°E, 28.80' - NAIL & TAG IN 13" RED OAK (OBT)  
S45°W, 53.46' - NAIL & TAG IN 11" TWIN MAPLE (OBT)  
S65°W, 21.44' - NAIL & TAG IN 16" RED OAK (OBT)

NOTE: K-13, T15N-R1W IS COMMON  
WITH K-1, T14N-R1W



Signed by Mark R. Robison  
Surveyor's Michigan License No. 27458

Date 12-19-96