

APPROVED LAND CORNER
 P.A. 345 OF 1990
 MIDLAND COUNTY

436

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970
 Midland County Remonumentation

STATE OF MICHIGAN
 MIDLAND COUNTY
 RECORDED

11/23/99

12/7/1999 2:59:31 PM

For Corners in
Midland
 (County)

	Located In:	Corner Code#:
1. Public Land Survey	T. <u>16N</u> R. <u>1W</u>	<u>M-13</u>
	T. <u>15N</u> R. <u>1W</u>	<u>M-1</u>
	T. _____ R. _____	_____
2. Public Controlling in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
3. Miscellaneous Property in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

SCOTT I. HAINES
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on October 28, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.
 T16N, R1W, M-13 & T15N, R1W, M-1 are single common corner.

A. Description of original monument and accessories and/or subsequent restoration:

1830 Clarke
 Post Cor T15 & 16N, R1W
 Pine 12 N23W 37
 B. Ash 14 S66W 23

1831 GLO
 West between 4 & 9 T15N, R1E
 73.99 Int. Mer. 8.67 N

1978 Schafer, (132) 2-520 & LCRC #444
 Fd Brass plate in Mon. Box on West edge of pvm't
 N30W 122.65 Tag in T.P.
 N60W 76.5 Nail in P.P.
 S45W 116.92 Nail in Tw. 10" Oak

SURVEY &
 REMONUMENTATION

FEB 25 2000

SECTION

1954 Braidwood, MSHD Field Notes
 Fd 1" Iron pipe
 N88W 76.70 Tag in 6" elm
 S56° 30' W, 117.35 Tag in 4" elm
 N28-30W, 122.65 Tag in Te. Pole

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found MSHD mon in Mon. Box 10.5' W of C.L. M-30. Found one 1978 witness. Meas. North 570.82' to closing corner and North 2636.3 to M-12.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted MSHD brass capped monument in Mon. Box as Midland Co. Remon corner. Accepted as best available evidence of the original position of the corner.

Witnesses:
 N42°E, 119.22 N & T in 8" W. Pine
 East 216.22 N & T in P.P.
 S22°W, 129.76 N & T in 12" Maple
 N51°W, 76.74 N & T in P.P. (OBT)



Signed by *Mark R. Robison*
 Surveyor's Michigan License No. 27458

Date *11-29-99*