

# SURVEY & REMONUMENTATION

**APPROVED LAND CORNER  
P.A. 345 OF 1990  
MIDLAND COUNTY**

APR 28 1995

157

## COMMISSION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
MIDLAND COUNTY  
REMONUMENTATION & FILED

For corners in 428/94 989

7 DEC 94 8:24 A.M.

BEVERLY J THAYER  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

<u>MIDLAND</u> <small>(County)</small>	Located In:	Corner Code <u>M-7</u>
1. Public Land Survey	T <u>15N</u> R <u>1W</u>	<u>M-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2							
3												
4	7	8	9	10	11							
5												
6	18	17	16	15	14							
7												
8	19	20	21	22	23							
9												
10	30	29	28	27	26							
11												
12	31	32	33	34	35							
13												

I, PAUL B. LAPHAM, in a field survey on NOVEMBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:
- |   |  |
|---|--|
| 1852 AUSTIN BURT PGS. 144-145<br>OLD POST<br>WIT.-HEMLOCK 8" NORTH 25 LKS.<br>MAPLE 24" S64°W 90 LKS. | 10-72 SCHAFER, (132) L.1, PG.231<br>FOUND CORNER<br>WIT.-MONUMENT 49.7' WEST |
| 10-30-10 UNKNOWN, C.S.R. 300-301<br>SET PINE ROOT POST FOR CORNER<br>NO WITNESSES                     | 9-26-80 MERRY, (132) L.3, PG.132<br>FOUND STATE HIGHWAY MARKER               |
| 8-14-26 HOMER SNELL, FERRO'S SUBDMISION (PLAT) L.A. PG.13   |  |
| 12-13-66 M.D.O.T., R/W PLANS. 56-R-2<br>SEC. CORNER 13.08' W OF @ M-30                                |  |
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- FOUND STATE OF MICHIGAN CAP ON 3' LONG BAR. FOUND PLAT MONUMENT 49.7' WEST OF CORNER. EXCAVATED TO DEPTH OF 3 FEET & FOUND NO FURTHER EVIDENCE.

Accepted as best available evidence of the position of the original corner & replaced with Standard Monument.

Corner, M-7 was approved for remonumentation at a Peer Review Committee Meeting on 11-28, 1994

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-7; Corner common to Sections 13 & 24  
Set 5/8" x 18" re-rod with brass cap stamped "Midland Co. Remon. Cor. PS 9433" in Monument Box.

- WITNESSES:
- N45°E 1.2' - BURRIED CABLE SIGN POST
  - SOUTH 44.80' - GUARD RAIL POST
  - S30°W 68.40' - NAIL & TAG IN POWER POLE
  - N30°E 78.00' - NAIL & TAG IN W. PINE
  - WEST 50.10' - R.O.W. MARKER
  - WEST 49.70' - CONCRETE PLAT MONUMENT



Signed by Paul B. Lapham Date 12-01-94  
Surveyor's Michigan License No. 9433