

**REMON. COR. C-1, GENEVA TWP.  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**462**

For corners in  
Midland  
(County)

- |                                       |                          |            |
|---------------------------------------|--------------------------|------------|
| 1. Public Land Survey                 | T <u>15N</u> R <u>2W</u> | <u>C-1</u> |
|                                       | T ___ R ___              | _____      |
|                                       | T ___ R ___              | _____      |
|                                       | T ___ R ___              | _____      |
| 2. Property Controlling in Section    | S ___ T ___ R ___        | _____      |
| 3. Miscellaneous Property in Sec.     | S ___ T ___ R ___        | _____      |
|                                       | S ___ T ___ R ___        | _____      |
| 4. Lot No. _____, Recorded Plat _____ |                          |            |
| 5. Private Claims _____               |                          |            |

STATE OF MICHIGAN  
MIDLAND COUNTY  
REMONUMENTATION & FILED

12/15/1999 8:26:43 AM

SCOTT I. HAINES  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, RODNEY CLAYPOOL, in a field survey on June 6, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

A. Description of original monument and accessories and/or subsequent restoration:

C-1 Corner common to Sections 5 and 6 on North Town Line  
Survey by Glo, 1830, set post  
Survey by F. Gibbs, 1902  
Act 132 Survey by Lapham & Associates, 1982, found plow point, L3, P-582

SURVEY &  
REMONUMENTATION

FEB 09 2000

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-1 Corner common to Sections 5 and 6 on North Town Line  
Set 5/8" rod & brass cap on South Line T16N-R2W at Glo offset distance. 72 lk, 47.52', no corner found, new CMP under road at corner location, (All old witnesses are gone)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-1 Corner common to Sections 5 and 6 on North Town Line  
Set 5/8" rod and brass cap stamped Midland Co. Remon Cor PS 29241, in monument box, and is accepted as the best available evidence of the position of the accepted corner.  
N 5 Deg W, 36.55', nail & plastic disc in Southwest face power pole  
S 10 Deg W, 42.27', nail & plastic disc in West face power pole  
S 70 Deg W, 96.52', nail & plastic disc in power pole  
N 70 Deg E, 77.82', Southeast corner top telephone box  
East, 47.52', C-13, T16N-R2W

Signed by Rodney D. Claypool  
Surveyor's Michigan License No. 29241

Date 12-11-99

Form approved by Michigan State Board of Land Surveyors, Jan. 28, 1971  
Revised May 14, 1971  
Revised Jan., 1983

APPROVED LAND CORNER  
P.A. 345 OF 1990  
MIDLAND COUNTY

9/17/99

