

JAN 21 1999

APPROVED LAND CORNER  
P.A. 345 OF 1990  
MIDLAND COUNTY

**REMON. CORNER C-2, GENEVA TWP SECTION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

**388**

For corners in  
MIDLAND  
(County)

1. Public Land Survey	Located in: T <u>15N</u> R <u>2W</u>	Corner Code # <u>C-2</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN  
MIDLAND COUNTY  
REMONUMENTATION & FILED

12/16/1998 12:11:56 PM

BEVERLY J. THAYER  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, RODNEY CLAYPOOL, in a field survey on June 6, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

- C-2 1/4 Corner common to Sections 5 and 6
- Survey by Glo, H. Park, 1831, set post  
Survey by F. Gibbs, 1902  
Survey by Lapham & Associates, 1982, found spike  
Survey by Ayres Associates, 1992, found pk nail  
LCRC by P. Lapham, 1983, found spike



**WITNESS NOTE:** Witnesses from above surveys and LCRC's are available in dossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- C-2 1/4 Corner common to Sections 5 and 6
- Found pk nail per surveys by Lapham & Associates, Ayres Associates and LCRC by P. Lapham. Dug 3', I found nothing.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- C-23 1/4 Corner common to Sections 5 and 6
- Found pk nail per surveys by Lapham & Associates, Ayres Associates and LCRC by P. Lapham; replaced nail with 5/8" rerod and brass cap stamped Midland Co. Remon cor PS 29241, in monument box, and is accepted as the best available evidence of the position of the accepted corner.
- N 30 Deg W, 84.85 ft, nail in 6" Ash  
S 30 Deg E, 66.83 ft, nail and plastic disc in 5" Oak  
N 40 Deg E, 58.87 ft, nail and plastic disc in 8" Pine  
West, 0.55 ft, centerline bit. road  
On line with fence to West.

Signed by Rodney D. Claypool

Date 12-04-98

Surveyor's Michigan License No. 29241