

SURVEY & REMONUMENTATION

FEB 09 2000

**REMON. COR. C-5, GENEVA TWP.
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

464

SECTION

For corners in
Midland
(County)

Located in:	<u>T 15N R 2W</u>	Corner Code #	<u>C-5</u>
	T ___ R ___		_____
	T ___ R ___		_____
	T ___ R ___		_____
	T ___ R ___		_____
	T ___ R ___		_____
	T ___ R ___		_____
	T ___ R ___		_____

STATE OF MICHIGAN
MIDLAND COUNTY
REMONUMENTATION & FILED

12/15/1999 8:26:43 AM

SCOTT I. HAINES
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

1. Public Land Survey
2. Property Controlling in Section
3. Miscellaneous Property in Sec.
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, **RODNEY CLAYPOOL**, in a field survey on June 18, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

A. Description of original monument and accessories and/or subsequent restoration:

C-5 Corner common to Sections 7, 8, 17 and 18

Survey by Glo, 1830's, set post
 Survey by F. Gibbs, 1903, post stone around
 Survey by P. Lapham, 1975, 1985, set 1/2" capped rerod
 Survey by J. Jones, 1996, found 5/8" rod & plug
 LCRC by P. Lapham, 1975, set 1/2" capped rerod
 LCRC by T. Mueller, 1978, found 1/2" capped iron
 LCRC by G. Smith, 1997, replace 12mm iron with 12mm iron & cap #14102 in monument box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-5 Corner common to Sections 7, 8, 17 and 18

Found 1/2" rod and cap # 14102 in monument box (new bituminous road) per surveys by P. Lapham, J. Jones and LCRC by P. Lapham, T. Mueller and G. Smith.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-5 Corner common to Sections 7, 8, 17 and 18

Replaced rod and cap with 5/8" rod and brass cap stamped Midland Co. Remon Cor PS 29241 and is the best available evidence of the position of the accepted corner.

N 45 Deg E, 50.15', pk nail in power pole (Rec)
 N 45 Deg W, 59.96', NW corner telephone box 1' above ground (Rec)
 N 60 Deg W, 97.22, nail in 24" Cottonwood
 S 45 Deg W, 75.56, PK nail in power pole (Rec)
 S 45 Deg W, 77.63', nail and disc in power pole stub
 On centerline all roads

Signed by Rodney D. Claypool
 Surveyor's Michigan License No. 29241

Date 12-11-99

Form approved by Michigan State Board of Land Surveyors, Jan. 28, 1971
 Revised May 14, 1971
 Revised Jan., 1983

APPROVED BY THE BOARD
 P.A. 345 OF 1990
 MIDLAND COUNTY

9/17/99

