

**APPROVED LAND CORNER
P.A. 345 OF 1990
MIDLAND COUNTY**

OCT 0 3 1996

**REMON. COR. G-4, GENEVA TWP.
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

COMMISSION 255

4/23/96 JDP

For corners in
Midland
(County)

Located in:	Corner Code #
T 15N R 2W	G-4
T ___ R ___	_____
T ___ R ___	_____
T ___ R ___	_____
S ___ T ___ R ___	_____
S ___ T ___ R ___	_____
S ___ T ___ R ___	_____
S ___ T ___ R ___	_____

STATE OF MICHIGAN
MIDLAND COUNTY
REMONUMENTATION & FILED

22 AUG 96 8:04 A.M.

BEVERLY J THAYER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

1. Public Land Survey
2. Property Controlling In Section
3. Miscellaneous Property in Sec.
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A B C D E F G H I J K L M

2	6	5	4	3	2	1
3						
4	7	8	9	10	11	12
5						
6	18	17	16	15	14	13
7						
8	19	20	21	22	23	24
9						
10	30	29	28	27	26	25
11						
12	31	32	33	34	35	36
13						

I, RODNEY CLAYPOOL, in a field survey on MARCH 28, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G-4 Corner common to Sections 9 and 10
- Survey by Government, 1830's, set wood post
 Survey by F. Gibbs, 1900, gas pipe
 Survey by H. Gilbert, 1989, found "T" bar
 Survey by H. Fluharty, 1990, found "T" bar
 LCRC by J. Campbell, 1979, found 1/2" pipe raised with "T" bar



WITNESS NOTE: Witnesses from above surveys and LCRC's are available in dossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- G-4 Corner common to Sections 9 and 10
- Found "T" bar on top of 1/2" pipe, replaced "T" bar with 5/8" rod and brass cap, per surveys by F. Gibbs, H. Gilbert, H. Fluharty, and LCRC by J. Campbell.

Corner G-4 was approved for remonumentation at a Peer Review Committee Meeting on 4/23/96.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-4 Corner common to Sections 9 and 10
- Found "T" bar on top of 1/2" pipe, replaced with 5/8" rod and brass cap stamped Midland Co. Remon Cor. PS 29241 in mon box per surveys by F. Gibbs, H. Gilbert, H. Fluharty, and LCRC by J. Campbell; and is accepted as the best available evidence of the position of the original corner.
- N 45 Deg E, 79.89', nail and disc in power pole
 N 47 Deg E, 33.18', nail and disc in light pole
 S 43 Deg W, 120.08', NE corner planter on east side house
 S 45 Deg W, 120.55', NE corner house (block)
 S 45 Deg E, 52.45', centerline 2" pipe (underground pipe line marker)

Signed by Rodney D. Claypool

Date 05-10-96

Surveyor's Michigan License No. 29241