

FEB 24 1998

APPROVED LAND CORNER  
P.A. 345 OF 1990  
MIDLAND COUNTY

MIDLAND COUNTY REMONUMENTATION SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

340

8/01/97 *MR*

For corners in

MIDLAND (County)	Located In:	Corner Code #
1. Public Land Survey	T 15N R 2W	G-5
	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN  
MIDLAND COUNTY  
FILED &  
REMONUMENTATION  
11 DEC 97 11:59 A.M.  
  
BEVERLY J THAYER  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, MARK R. ROBISON, in a field survey on July 1, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1830 Wright  
Wit.-Hemlock 10 N52E 27 lks  
Sugar 14 S42W 34 lks  
Undated C.S.R. field notes, C.S.R.  
Set 1 1/2" Gas Pipe  
North 40.01 to G-4  
East 40.15 to H-5  
8-18-73 Loukus, L.C.R.C. 232  
Fd. 5/8" rod  
Wit.-S45E 37.00 20" Oak  
N30E 42.61 T.P.

N55E 59.70 13" Maple  
10-29-73 Urbaniak (132) 1-533  
Fd. 1 1/4" Pipe  
Wit.-N15E 42.6 T.P.  
N55E 57.6 12" Maple  
S40E 36.9 24" Maple  
2-14-74 Lapham, L.C.R.C. 276  
Wit.-same as 10-29-73  
6-22-78 Gilbert (132) 2-611  
Wit.-same as 8-18-73  
East 2640.0 to 1/4 Cor?

9-7-83 McGinnis (132) 3-506  
Wit.-same as 10-29-73  
South 2647.79 to 1/4 Cor  
West 2636.05 to 1/4 Cor  
9-7-83 McGinnis (132) 3-505  
Wit.-same as 10-29-73

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1 1/2" pipe & two OBT's. The 12" Maple is a stump at N64E 57.6. Searched but did not find 5/8" rod referred by Loukus, but one Loukus witness seems to fit 1 1/2" Pipe. Meas. North 2646.98 to G-4 (C.S.R. 2640.66).

Corner, G-5 was approved for remonumentation at a Peer Review Committee Meeting on August 1, 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 18" Gas Pipe with Brass Cap stamped "Midland Co. Remon. Cor. P.S. 27458" in Monument Box. Accepted as perpetuation of C.S.R. Corner.

Witnesses:  
N53E 58.60', nail & tag, 30" Maple (OBT)  
S24W 83.18', nail & tag, P.P.  
S79E 107.98', nail & tag, 20" Apple Tree  
S40E 36.90', nail & tag, 36" W. Oak (OBT)

Signed by Mark R. Robison  
Surveyor's Michigan License No. 27458

Date 10-31-97

