

APPROVED LAND CORNER
P.A. 345 OF 1990
MIDLAND COUNTY

MIDLAND COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

341

8/21/97
For corners in

<u>MIDLAND</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>15N</u> R <u>2W</u>	<u>H-1</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
MIDLAND COUNTY
FILED &
REMONUMENTATION
11 DEC 97 11:59 A.M.

BEVERLY J THAYER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, MARK R. ROBISON, in a field survey on July 1, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:
 Corner not set in G.L.O. survey
 8-15-03 Gibbs, C.S.R.
 Set Cedar Post
 Wit.-N54E 69 Pine Stump
 S24E 62 Pine Stump
 East 40.16 to I-1
 West 40.16 to G-1
 6-2-71 Lapham (132) 1-003
 Witnesses Std. Corner Sec 34
 4-7-72 Schafer (132) 1-85
 No corner material noted
 East 42.24' to Std. Cor.
 7-31-72 Sedgman
 Witnesses Std. Corner Sec 34

SURVEY &
REMONUMENTATION

FEB 24 1998

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found 1/2" iron. Measured East 42.11 (Schafer 42.24) to Standard Corner. West 2649.72 to G-1 (CSR 2650.56).

Corner, H-1 was approved for remonumentation at a Peer Review Committee Meeting on August 1, 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set 3/4" x 18" Gas Pipe with Brass Cap stamped "Midland Co. Remon. Cor. P.S. 27458" in Monument Box. Accepted as best available evidence of the accepted position of the corner.

Witnesses:
 East 42.11' Standard 1/4 Corner
 S38E 55.12', nail & tag, 8" Red Pine
 N40W 77.06', nail & tag, P.P.
 S30W 137.46', nail & tag, P.P.

Signed by Mark R. Robison
 Surveyor's Michigan License No. 27458

Date 10-31-97

